



RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION: 0022 - M STORE

CLOSING DATE : 06.06.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	INSTALLATION OF 2 X 21 TR SKM MAKE PACKAGE	1	G01				
			AC UNITS IN PLACE OF 2 SETS OF SUPPLY AIR						
			FANS & EXHAUST AIR FANS AT THE ROOFTOP OF						
			CENTR						
			AL CONTROL BUILDING (M-STN) FOR SERVING THE						
			CABLE BASEMENT. FINAL TESTING &						
			COMMISSIONING SHALL ALSO BE DONE. SCOPE						
			OF WORK: 1.#REM						
			OVAL OF EXISTING 2 X EXHAUST AIR FANS & 2 X						
			SUPPLY AIR FANS AND HANDOVER TO DEWA AT						
			GROUND FLOOR. 2.#INSTALLATION OF PACKAGE						
			AC UNIT						
			S (1 DUTY+ 1 STANDBY) WITH BELOW						
			SPECIFICATIONS BOUGHT ALREADY BY DEWA.						
			MAKE: SKM; MODEL: APMR52300G1; CAPACITY: 21						
			TR; FLOW RATE: 9						
			000 CFM; QTY: 2 NOS. ELECTRICAL SUPPLY: 3PH						
			380VAC. WEIGHT OF THE UNITS: 2.6 T 3.#DESIGN,						
			SUPPLY AND INSTALLATION OF STEEL STRUCTURE						
			FOUNDATION FOR THE PACKAGE AC UNITS AT						
			ROOFTOP. THESE MAY BE FIXED ON THE EXISTING						
			INVERT RC BEAMS. 4.#SUPPLY AND INSTALLATION						
			OF 1						





RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION : 0022 - M STORE

CLOSING DATE : 06.06.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SET OF PLENUM BOXES MADE OF GI SHEETS 50						
			MM THICK RUBBER INSULATION, FOSTER, CLOTH						
			AND 0.8 MM THICK ALUMINUM CLADDING TO						
			CONNECT TH						
			E SUPPLY & RETURN AIR DUCTS OF BOTH UNITS.						
			5.#SUPPLY AND INSTALLATION OF NRD IN SUPPLY						
			AIR DUCT. 6.#SUPPLY AND INSTALLATION OF GI DU						
			CT WITH INSULATION AND ALUMINUM CLADDING						
			TO CONNECT EXISTING ROOM DUCTS WITH THE						
			PLENUM BOXES. RUBBER INSULATION 50 MM						
			THICKNESS AND						
			ALUMINUM 0.8 MM THICKNESS. 7.#SUPPLY AND						
			INSTALLATION OF HOT DIPPED GALVANIZED						
			SUPPORTS FOR DUCTS (WHEREVER REQUIRED)						
			AS PER THE ST						
			ANDARDS. 8.#SUPPLY AND INSTALLATION OF						
			RUBBER INSULATION WITH ALUMINUM CLADDING						
			FOR RETURN AIR DUCT FROM ROOF TO ROOM						
			(APPROX. 320 S						
			Q. MTR) WITH OUTDOOR DUCT INSULATION OF 50						
			MM THICKNESS AND INDOOR DUCT INSULATION OF						
			25 MM THICKNESS. 9.#FRESH AIR MANUAL						
			DAMPERS W		1				





RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION: 0022 - M STORE

CLOSING DATE : 06.06.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			ITH LOUVERS 250 X 250 MM SHALL BE INSTALLED						
			ON THE ROOF TOP WITH ALUMINUM FILTER.						
			10.#DUCT CLEANING FOR INDOOR AREAS						
			11.#MODIFICATIO						
			N OF SUPPLY AIR REGISTER GRILL (1 NO.) FROM						
			SIDE THROW TO BOTTOM THROW IN THE						
			BASEMENT ROOM. 12.#SUPPLY AND INSTALLATION						
			OF POWER IS						
			OLATOR IP65 100A NEAR TO THE UNITS WITH						
			CABLE CONNECTIONS TO THE PACKAGE UNIT. ALL						
			CABLE AND WIRES WILL BE LAID IN CABLE TRAY						
			AND CO						
			NDUITS. 13.#SUPPLY AND INSTALLATION OF NEW						
			THERMOSTAT WITH CONTROL CABLING FOR 2.0						
			NOS PACKAGE ACS AT CABLE BASEMENT ROOM						
			(ABOUT 50M						
			DOWN FROM ROOFTOP) 14.#SUPPLY AND						
			INSTALLATION OF XLPE ARMORED POWER CABLES						
			FROM SPARE FEEDERS AVAILABLE IN 3RD FLOOR						
			HVAC MCC ROOM						
			TO THE NEW ROOF CONTROL PANEL (DISTANCE IS						
			ABOUT 100 M) WITH CABLE TRAY/ TRUNKS.						
			EXISTING TRAY MAY BE USED WHEREVER						





RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION: 0022 - M STORE

CLOSING DATE : 06.06.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			APPLICABLE WITH						
			DEWA#S APPROVAL. 15.#SUPPLY AND						
			INSTALLATION OF PVC DRAIN PIPE TO THE						
			NEAREST DRAIN POINT. 16.#MONITORING,						
			CONTROL AND CHANGEOVER O						
			PTION BETWEEN DUTY & STANDBY UNITS SHALL						
			BE PROVIDED IN THE EXISTING SIEMENS MAKE						
			BMS SYSTEM. EXISTING BMS LOGIC FOR THE						
			REMOVED SUP						
			PLY/ EXHAUST FANS MAY BE USED FOR THE						
			ABOVE. NECESSARY CONTROL CABLES SHALL BE						
			LAID FROM THE AC UNIT/ SWITCHGEAR TO THE						
			BMS/DDC PANE						
			L (LOCATED ON THE SAME FLOOR). 17.# TESTING						
			AND COMMISSIONING OF THE PACKAGE A/C UNITS.						
			18.#DEWA WILL PROVIDE THE SCAFFOLDING AND						
			CR						
			ANE FACILITIES, AS REQUIRED. 19.#BIDDERS						
			SHALL MAKE SITE VISIT BEFORE QUOTING TO						
			DETAIL SURVEY THE SITE AND JOB						
			REQUIREMENTS. WITHO						
			UT SITE VISIT, NO QUOTATION WILL BE						
			ENTERTAINED. CONTACT PERSON: MR. MUMTAZ						





RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION: 0022 - M STORE

CLOSING DATE : 06.06.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ALI ABRO, ENGR-EM, 055-6471260,						
			MUMTAZ.ABRO@DEWA.GOV.AE						
) 20.#BIDDER SHALL SUBMIT THE FOLLOWING						
			ALONG WITH THEIR QUOTE FOR EVALUATION:						
			A.#GAD OF THE UNIT SETUP AND DUCTS.						
			B.#ELECTRICAL DR						
			AWING. C.#BILL OF MATERIALS WITH DATASHEETS.						
			D.#SUPPORTING LOAD CALCULATION SHEETS.						
			21.#BIDDER SHALL SUBMIT THE FOLLOWING AFTER						
			COM						
			PLETION OF THE JOB FOR DEWA APPROVAL: A.#AS						
			BUILT GAD OF THE UNIT SETUP AND DUCTS. B.#AS						
			BUILT ELECTRICAL DRAWING. C.#AS BUILT BILL						
			OF MATERIALS WITH DATASHEETS. D.#AS BUILT						
			SUPPORTING LOAD CALCULATION SHEETS.						
			E.#TESTING & COMMISSIONING RECORDS. 22.#ANY						
			OTHER JOBS						
			, WHICH ARE NOT MENTIONED ABOVE, BUT MAY						
			REQUIRE AT SITE FOR SUCCESSFUL COMPLETION						
			OF THE PROJECT SHALL BE ARRANGED BY THE						
			CONTRACTO						
			R.						





RFQ NUMBER : 2332301223

DATE : 31.05.2023 **REQ No** : 1032301646

REQ TITLE : TR Package A/C units

DELIVERY LOCATION: 00

: 0022 - M STORE

CLOSING DATE : 06.06.2023

CLOSING TIME : 10:00:00

TOTAL AMOUNT IN WORDS: TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

TR Package A/C units

STANDARD TERMS & CONDITIONS

- 1) Prices should be 'DDP' delivery duty paid at DEWA stores.
- 2) Quotation to be submitted only in local currency U.A.E Dirhams
- 3) DEWA Standard payment terms is '30 days credit' from the date of acceptance of material
- 4) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.
- 5) The offered product and/ or services in the Quotation, shall be conforming and in accordance with DEWA Energy Management Policy & EnMS Manual.

SUPPLIER'S REMARKS:

SUPPLIER'S SIGNATURE AND STAMP