

RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	TECHNICAL SPECIFICATIONS, TERMS &	5.060	М				
			CONDITIONS AND SCOPE OF WORK FORREMOVAL						
			OF EXISTING ARMORED CABLE, TRENCH						
			EXCAVATION, INSTALLATION						
			OFCABLE, BACK FILLING WITH AEOLIAN SAND AND						
			SUPPLY & INSTALLATION OF SABKHA SOIL ALONG						
			THE CABLE ROUTE AT WELL FIELD AREA.REF						
			DEWA P						
			RJ NO:A.#GENERALTHE SUBJECT ACTIVITY HAS						
			BEEN INITIATED TO PROTECT DEWA ASSETS IN						
			THEEXISTING WELL FIELDS AREA IN MURGHAM,						
			NAZWA, HA						
			BAB AND WAHOOSH.THIS WORK INCLUDES THE						
			FOLLOWING: #IDENTIFYING THE CABLE ROUTE						
			FROM PUMP HOUSE TO LOCAL						
			STARTER-#CHECKING THE SURROU						
			NDINGS OF EXISTING LOCAL						
			STARTERS.#EXCAVATION, INSTALLATION, AND						
			BACKFILLING WITH SABKHA/ WHITE SOILWARNING						
			TAPES AS PER DEWA STANDA						
			RD CABLE INSTALLATION PROCEDURE IN						
			THEGROUND AND RE-TERMINATION AT BOTH ENDS						
			AS PER BOQ AND SCOPE OF WORK.MAIN POWER						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FEEDER CABLE DE						
			TAILS: LOW VOLTAGE ARMORED CABLE; 4C X						
			50SQ.MM, XLPE/ PVC INSULATED; STEEL WIRE						
			ARMOUR, COPPER CABLE.LOCATION, WELL NO &						
			CABLE LENG						
			TH DETAILS: REFER BOQLENGTH MENTIONED AS						
			PER BOQ ARE APPROXIMATE. THE ACTUAL						
			LENGTH MAYCHANGE AS PER THE SITE CONDITION						
			INCLUDING RE						
			-ROUTING. PAYMENT SHALL BEMADE BASED ON						
			ACTUAL LENGTH AFTER INSTALLATION JOB						
			COMPLETED AND SHALLBE SUBMITTED TO DEWA						
			WITH EVIDENCE F						
			OR APPROVAL.B.#GENERAL TERMS AND						
			CONDITIONS1.#THE CONTRACTOR MUST BE ISO						
			9000 & ISO 14000 CERTIFIED COMPANY.2.#THE						
			CONTRACTOR SHALL						
			HAVE OFFICE / BUSINESS SETUP WITHIN						
			UAE.3.#THE CONTRACTOR SHALL HAVE REQUIRED						
			4-WHEEL MACHINERY / TESTINGEQUIPMENT /						
			TOOLS TO CARRY						
			OUT THE WORK.4.#THE CONTRACTOR SHALL HAVE						
			STAFF HAVING EXPERIENCE OF SIMILARACTIVITIES						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			WITHIN UAE. SUBMIT LIST OF WORKING PEOPLE						
			FOR						
			THIS PROJECTALONG WITH CV ALONG WITH THE						
			OFFER.5.#THE CONTRACTOR MUST SUBMIT						
			REFERENCES OF SIMILAR TYPE OF ACTIVITIES/						
			MAINTENANCE						
			WORKS DONE ALONG WITH THE OFFER.6.#SITE						
			VISIT IS MANDATORY FOR ALL CONTRACTORS						
			PRIOR TO SUBMITTINGQUOTATION.7.#THE SCOPE						
			INCLUDES SU						
			PPLY AND INSTALLATION OF WARNING TAPE &						
			SABKHASOIL.8.#SUPPLY OF WATER FOR						
			COMPACTION OF SABKHA SOIL SHALL BE						
			INCONTRACTOR#S SCOPE.9.						
			#THE CONTRACTOR SHALL BE RESPONSIBLE FOR						
			SOURCING AND TRANSPORTATIONOF SABKHA						
			SOIL TO THE WORK SITE.10.#THE CONTRACTOR						
			SHALL INFORM						
			DEWA ENGINEER WHEN SABKHA SOIL ISSOURCED.						
			DEWA ENGINEER SHALL CHECK AND CONFIRM						
			ACCEPTANCE OF QUALITY OFTHE SABKHA SOIL.						
			THE SABKHA						
1			SOIL SHALL BE TRANSPORTED TO SITE ONLY						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AFTERCONFIRMATION FROM DEWA						
			ENGINEER.11.#THE CONTRACTOR SHALL FOLLOW						
			ALL SAFETY REQUIREMENTS						
			DURINGHANDLING, TRANSPORTATION AND						
			REPAIRING.12.#ON RECEIVING THE LPO, THE						
			CONTRACTOR SHALL OBTAIN NECESSARY NOC						
			/APPROVAL FROM ALL						
			STATUTORY DEPARTMENTS PRIOR TO START OF						
			EXECUTION, IFREQUIRED; NOC DOCUMENTS						
			/PAPER SHALL SUBMIT TO DEWA						
			REPRESENTATIVEBEFORE PROCEE						
			DING OF ANY JOB AT SITE.13.#THE CONTRACTOR						
			SHALL PROVIDE ADEQUATE MEANS FOR						
			TRANSPORTATION OFALL NECESSARY						
			EQUIPMENT#S AND MACHINERI						
			ES FROM THEIR SITE TO DEWA SITEAND						
			VICE-VERSA. LOADING AND UNLOADING AT THE						
			SITE IS CONTRACTOR'S SCOPEHENCE, ALL RISKS						
			AT THEIR OWN						
			COST.14.#LIFTING EQUIPMENT AND MACHINERY						
			SHALL BE ARRANGED BY CONTRACTOR.C.#SCOPE						
			OF WORK: C1 # IDENTIFICATION OF CABLE						
			ROUT						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE: service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			E & CABLE TRENCH EXCAVATION (1MWIDTH X 1M						
			DEPTH)1.#THE CONTRACTOR SHALL ACCESS AND						
			LOOK FOR ANY NEARBY PIPELINE,						
			VALVECHAMBER, UNDER						
			GROUND CABLE, OVERHEAD LINE, ROAD						
			CROSSING OR ANYGOVERNMENT AND PRIVATE						
			PROPERTY BEFORE EXECUTION OF JOB. IF						
			FOUND, THECONTRACTOR S						
			HALL IMMEDIATELY INFORM THE DEWA						
			REPRESENTATIVE.2.#CONTRACTOR SHALL USE						
			APPROPRIATE MEANS FOR IDENTIFICATION OF						
			CABLEROUTE FROM PUMP						
			HOUSE TO LOCAL STARTER.3.#EXCAVATION OF						
			THE CABLE TRENCH ALONG THE CABLE ROUTE BY						
			ONE METERDEPTH X 1 METER WIDE BY						
			APPROPRIATE MACH						
			INERY.4.#IF ANY CABLE/ ROAD / VALVE CHAMBER /						
			PIPELINE OR ANY OTHERGOVERNMENT OR						
			PRIVATE PROPERTY IS DAMAGED DURING THE						
			WORK, THECON						
			TRACTOR SHALL BE HELD RESPONSIBLE. IN SUCH						
			CASE, THE CONTRACTOR SHALLREPAIR / REPLACE						
			THE SAME AS SOON AS POSSIBLE WITHOUT ANY						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			EXTRA						
			COST TODEWA AND PAY ANY FINES ASSOCIATED						
			WITH THE DAMAGE.5.#ALL POWER CABLES SHALL						
			BE DISCONNECTED FROM BOTH END AND FIX						
			WARNINGTAG						
			JOINTLY WITH DEWA ENGINEER BEFORE						
			STARTING ANY EXCAVATION. C2 #						
			INSTALLATION OF CABLE, BACK FILLING,						
			COMPACTION & TESTING1.#						
			INSTALLATION OF DEWA SUPPLIED NEW						
			4CX50SQMM, XLPE/PVC, SWA, COPPERCABLE						
			FROM PUMP HOUSE TO LOCAL STARTER ALONG						
			THE NEWLY EXCAVATED T						
			RENCH.2.#BACKFILLING ABOVE THE CABLE WITH						
			AEOLIAN SAND UP TO 650MM FROMBOTTOM OF						
			THE TRENCH.3.#SUPPLY AND INSTALLATION OF						
			WARNING TA						
			PE THROUGHOUT THE CABLE ROUTEIS						
			REQUIRED.4.#SUPPLY AND INSTALLATION OF						
			SABKHA SOIL ABOVE THE WARNING TAPE BY						
			0.3METER HIGH X 1 METER						
			WIDE INCLUDING LEVELING AND PROPER						
			COMPACTION.5.#CONNECTION OF THE CABLE AT						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			LV PANEL IN PUMP HOUSE AND LOCAL						
			STARTERSSHALL BE WITHI						
			N THE CONTRACTOR#S SCOPE OF WORK.6.#AFTER						
			THE CABLE INSTALLATION, THE CONTRACTOR						
			MUST ARRANGE A JOINTINSPECTION WITH DEWA						
			ENGINEER T						
			O DETERMINE THE CONDITION OF THE CABLE						
			/EXTENT OF DAMAGE & REPAIR REQUIRED. THE						
			OBSERVED DEFECTS SHALL BE NOTEDAND						
			SIGNED JOINTLY BY						
			CONTRACTOR SUPERVISOR/ REPRESENTATIVE						
			AND DEWAENGINEER AT SITE.7.#DEWA						
			REPRESENTATIVE(S) SHALL BE INFORMED WHEN						
			THE FINAL INSPECTIO						
			NAND TESTING OF THE CABLE IS TO TAKE PLACE.						
			FINAL INSPECTION AND FINALTEST AFTER THE						
			CABLE INSTALLATION/REPAIR SHALL BE						
			CONDUCTED I						
			N THEPRESENCE OF DEWA						
			ENGINEERS.8.#LEVELING AND PROPER						
			COMPACTION WITH WATER AND APPROPRIATE						
			MACHINERYSHALL BE WITHIN THE CONTRACTOR						
			#S SCOPE OF WORK.D.#FINAL TEST AT SITE:AFTER						



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			COMPLETION OF THE JOB, CABLE SHALL BE ASSESSED FOR THE FOLLOWING. IF ANYTHING, ABNORMAL RELATED TO THE CABLE, THE CONTRACTOR MUST RECTIFY/ REPLACE THE CABLE WITHOUT ANY EXTRA COST TO DEWA. #VISUAL INSPECTION OF THE NEW CABLE ROUTES. #MEGGER TEST FOR ANY GROUND FAULT. #CONTINUITY TEST. #LOAD TEST BY RUNNING THE PUMPS. AFTER COMPLETION, SERVICE REPORT SHALL BE PREPARED BY THE CONTRACTOR AND SUBMITTED FOR APPROVAL BY DEWA ENGINEER.						

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:



RFQ NUMBER : 2332402321

DATE : 12.09.2024

REQ No : 1032403938

REQ TITLE : service 1032403938

DELIVERY LOCATION

CLOSING DATE : 20.09.2024

CLOSING TIME : 10:00:00

STANDARD TERMS & CONDITIONS

- 1) Prices should be 'DDP' delivery duty paid at DEWA stores.
- 2) Quotation to be submitted only in local currency U.A.E Dirhams
- 3) DEWA Standard payment terms is '30 days credit' from the date of acceptance of material
- 4) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.
- 5) The offered product and/ or services in the Quotation, shall be conforming and in accordance with DEWA Energy Management Policy & EnMS Manual.

СI	IDDI	פיסשו	RKS:

SUPPLIER'S SIGNATURE AND STAMP