

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	MOBILIZATION & SITE SURVEY:AS PART OF THE MOBILIZATION AND SITE SURVEY SHALL BE DONE BY THECONTRACTOR TO OBTAIN THE BUILDING MANAGEM ENT PERMISSION, NOCS FROM DEWAWATER/ELECTRICITY, DM, ETISALAT AND RTA AS PER THE REQUIREMENTS OF THEPROJECT & DEWA SPECIFICATIONS.CO NTACT: SHEIKH MONIR HOSSAIN / +971526868807 & MUHAMMAD ASIF AKHTAR/+971508725087SITE VISIT: 02.07.2025PAYMENT TERMS: 100% OF WORKS/ RETENTION: 5%	250	EA				
2		ITEM-00001	PVC CABLE CONDUITS WORKS FOR INTERLOCK SURFACE:REMOVE ALL TYPES OF EXISTING INTERLOCK, SURFACES, OR PAVEMENT, ANDPERFORM EXCAVATION AS REQUIRED. THE WIDTH AND DEPTH OF THE TRENCH SHALLBE 400 MM. AFTER EXCAVATION, TWO (02 NO.) 25 MM PCV CONDUITS WITH GICOUPLING AC CESSORIES, 4 MM NYLON ROPE SHALL BE INSTALLED ACCORDING TOTHE PROJECT	2,600	RM				

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SPECIFICATIONS. SAFETY MARKINGS, SAFETY TAPE, CAUTION SIGNS, BACKFILLING, COMPACTION, AND INTERLOCK PAVEMENT REINSTALLATION SHALL BE PERFORMED IN ACCORDANCE WITH THE BUILDING OWNER'S APPROVAL DEWA SPECIFICATIONS AND INSTRUCTIONS PROVIDED BY THE DEWA ENGINEER.						
3		ITEM-00001	PVC CABLE CONDUITS WORKS FOR LANDSCAPE/ROAD BASE/SOIL SURFACE: MANUAL EXCAVATION WORK SHALL BE PERFORMED BY THE CONTRACTOR FROM DEWA BULK WATER METER TO THE BUILDING LV ROOM. THE WORK SHALL BE CARRIED OUT AT THE EXISTING GROUND LEVEL, WHICH CONSISTS OF LANDSCAPE AREA, ROADBASE AND SOIL SURFACE OR GREEN AREAS. THE WIDTH AND DEPTH OF THE TRENCH SHALL BE 400 MM. AFTER THE EXCAVATION, TWO (02 NO.) 25 MM PVC CABLE CONDUITS WITH 4 MM NYLON ROPE SHALL BE INSTALLED ACCORDING TO THE PROJECT SPECIFICATIONS. SAFETY	300	RM				

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			MARKINGS, SAFETY TAPE, CAUTION SIGNS, BACKFILLING, COMPACTION, AND LANDSCAPE GREEN AREAS ROAD BASE REINSTALLATION SHALL BE PERFORMED IN ACCORDANCE WITH THE BUILDING OWNER'S APPROVAL, DEWA SPECIFICATIONS AND INSTRUCTIONS PROVIDED BY THE DEWA ENGINEER.						
4		ITEM-00001	PVC CABLE CONDUITS WORKS FOR CONCRETE SURFACE: THE EXISTING CONCRETE SURFACE / PAVEMENT SHALL BE CUT PROPERLY WITH THE CONCRETE CUTTER AND BROKEN USING A SPECIFIED JACKHAMMER. AFTER REMOVING THE CONCRETE, THE TEAM SHALL REACH THE PROPER DEPTH. THE WIDTH & DEPTH OF THE TRENCH SHALL BE 400 MM, AFTER THE EXCAVATION, TWO (02 NO.) 25 MM PVC CABLE CONDUITS WITH 4 MM NYLON ROPE SHALL BE INSTALLED ACCORDING TO THE PROJECT SPECIFICATIONS. SAFETY MARKINGS, SAFETY TAPE, CAUTION SIGNS, BACKFILLING, COMPACTION, AND	50	RM				

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CONCRETE SURFACE REINSTALLATION SHALL BE PERFORMED IN ACCORDANCE WITH THE BUILDING OWNER'S APPROVAL, DEWA SPECIFICATIONS AND INSTRUCTIONS PROVIDED BY THE DEWA ENGINEER.						
5		ITEM-00001	PVC CABLE CONDUITS WORKS FOR TILES / MARBLE SURFACE: THE EXISTING TILES OR MARBLES SURFACE SHALL BE REMOVED PROPERLY AND BROKEN WITH A SPECIFIED JACKHAMMER. AFTER THE EXCAVATION, TWO (02 NO.) 25 MM PVC CABLE CONDUITS WITH 4 MM NYLON ROPE SHALL BE INSTALLED ACCORDING TO THE PROJECT SPECIFICATIONS. SAFETY MARKINGS, SAFETY TAPE, CAUTION SIGNS, BACKFILLING, COMPACTION. THE MARBLE AND TILES SURFACES REINSTALLATION SHALL BE PERFORMED IN ACCORDANCE WITH THE BUILDING OWNER'S APPROVAL, DEWA SPECIFICATIONS AND INSTRUCTIONS PROVIDED BY THE DEWA ENGINEER.	50	RM				

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
6		ITEM-00001	INSTALLATION OF MANHOLE/PUL PIT CHAMBER:PRECAST PULL PIT/MANHOLE SHALL BE INSTALLED (300MM X 300MM X 400MM) ASREQUIRED WITH GRP SEALING PLATE BY THE CONTRACTOR.(INSTALLATION OF PULPIT/MANHOLE IF THE LENGTH MORE THAN 20.00M, OVER THE90 DEGREE BEND & REQUIRED) AS PER THE DRAWINGS DEWA SPECIFICATION ANDINSTRUCTION PROVIDED BY THE DEWA ENGINEER.	50	EA				

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

Supply, Excavation

STANDARD TERMS & CONDITIONS

- Prices should be 'DDP' delivery duty paid at DEWA stores.
- Quotation to be submitted only in local currency U.A.E Dirhams

MATERIAL AND OR SERVICE PROVIDED TO DEWA SHOULD PREFERABLY BE ENERGY EFFICIENT AND ENVIRONMENT FRIENDLY.

REQUEST FOR QUOTATION LOCAL PURCHASE SECTION

RFQ NUMBER : 2332501639
DATE : 01.07.2025
REQ No : 1032503045
REQ TITLE : Supply, Excavation 1032503045
DELIVERY LOCATION
CLOSING DATE : 07.07.2025
CLOSING TIME : 10:00:00

3) DEWA Standard payment terms is '30 days credit' from the date of acceptance of material

4) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

5) The offered product and/ or services in the Quotation, shall be conforming and in accordance with DEWA Energy Management Policy & EnMS Manual.

SUPPLIER'S REMARKS :

SUPPLIER'S SIGNATURE AND STAMP