REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	COMPLETE OVERHAULING OF BOOSTER PUMP FOR HATTA PH3 PUMPING STATION. PUMPDETAILS: AVERSA PUMP MODEL: DVL-350X300, HEAD-140M, FLOW-263 L/S,RPM-1475, 630KW.SCOPE OF WORKTHE FOLLOWING OUTLINES THE MANDATORY AND OPTIONAL SCOPE OF WORK FOR THEOVERHAUL OF BOOSTER PUMPS AN D THEIR ACCESSORIES AT THE BOOSTER PUMPINGSTATION.1.0 MANDATORY SCOPE OF WORK:A) THE CONTRACTOR IS RESPONSIBLE FOR TRANSPORTING THE PUMP ASSEMBLY TOAND FROM THE DEWA SITE TO THEIR WORKSHOP. DEWA WILL NOT PROVIDETRANSPORTATION. FOR LOADING AND UNLOADING, THE CONTRA CTOR MAY USE DEWA#SOVERHEAD CRANE AT THE PUMPING STATION, WITH PROPER COORDINATION WITHDEWA REPRESENTATIVES. B) REPLACEMENT OF THE M ECHANICAL SEAL, COUPLINGBUSH RENEWAL, GLAND PACKING RENEWAL, AND BEARING REPLACEMENT ASREQUIRED. C) OVERHAULING OF	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THE PUMP (REFER T O ANNEXURE I FOR MANDATORYAND ANNEXURE II FOR OPTIONAL WORK). D) EXTERNAL PAINTING OF THE PUMP. E)RECTIFICATION OF ANY ISSUES THAT A RISE AFTER INSTALLATION/LOAD TESTING.THIS SHALL BE DONE ON SITE IF POSSIBLE, AND IF NOT, THE CONTRACTOR ISRESPONSIBLE IN COLLECTING THE PUMP AND MOVED IT BACK TO THEIR FACILITY.F) IF ANY PART IS FOUND DEFECTIVE, THE CONTRACTOR IS RESPONSIBLE FORREPAIRING OR REPLAC ING IT. DEWA WILL PROVIDE AVAILABLE SPARES. IF ANYSPARE PARTS ARE UNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SUBMITTHE COST F OR DEWA APPROVAL BEFORE PLACING AN ORDER. G) ONCE THE PUMP ISFULLY ASSEMBLED, THE PUMP MUST BE PRESSURE HYDRO TESTED IN THECONTRACTO R FACILITY TO MAKE SURE THE PUMP IS WELL ASSEMBLED AND THATTHERE ARE NO LEAKS.2.0						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			REQUIREMENTS PRIOR TO QUOTATION SUBMISSION:A) THE CONTRACTOR MUST VISIT THE SITE TO FAMILIARIZE THEMSELVES WITH THESCOPE OF WORK AND POTENTIAL COMPLEXITIES BEFORE SUBMITTING A QUOTAT ION.B) DEWA WILL NOT ACCEPT ANY CLAIMS FOR ADDITIONAL CHARGES BEYOND THEAGREED RATES OR PRICES DURING OR AFTER THE EXECUTION OF THE WORK. C) THECONTRACTOR WILL BE PROVIDED WITH AN EQUIPMENT SHUTDOWN SCHEDULE INCOORDINATION WITH THE OPERATIONS & MAINTENANCE DEPARTM ENT OF THE WATERDIVISION. D) A TIME SCHEDULE OR BAR CHART SHOWING EACH ACTIVITY MUST BESUBMITTED. E) UPON COMPLETION, AN INSPECTION CHECKLIST AND QUALITYPROCEDURE DOCUMENTATION, WHERE APPLICABLE, MUST BE SUBMITTED. F) THECONTRACTOR IS RESPONSIBLE FOR SITE SUPERVIS ION, COORDINATION OF FIELDACTIVITIES, AND THE						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SUPPLY OF REQUIRED TECHNICIANS, TOOLS, EQUIPMENT,AND RESOURCES NECESSARY TO EXECUTE TH E CONTRACT.3.0 TAKEOVER:UPON COMPLETION OF ALL WORK WITHIN THE SCOPE OF THE CONTRACT, THECONTRACTOR MUST NOTIFY DEWA IN WRITING. A C ERTIFICATE OF COMPLETION WILLBE ISSUED AFTER A FINAL INSPECTION, CONFIRMING THAT THE WORK HAS BEENACCEPTED AND TAKEN OVER BY DEWA FO LLOWING THE NECESSARY CONDITIONMONITORING CHECKS.4.0 WARRANTY:A) ALL WORK WILL CARRY A WARRANTY OF 8,000 HOURS OF OPERATION OR ONEYE AR, WHICHEVER COMES FIRST. B) THE WARRANTY WILL TAKE EFFECT FROM THEDATE OF DEWA'S OFFICIAL TAKEOVER OF THE COMPLETED JOB. C) IF ANY DEFECTSARE IDENTIFIED DURING THE WARRANTY PERIOD, THE CONTRACTOR MUST RECTIFYTHEM WITHIN THE TIMEFRAME SET BY DEWA WITHOUT						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026
REQ No : 1032605314
REQ TITLE : Complete pump overhauling and
DELIVERY LOCATION
CLOSING DATE : 06.11.2026
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ADDITION AL COST ORCOMPENSATION.5.0 DOCUMENTATION:UPON SATISFACTORY COMPLETION OF THE WORK AND HANDOVER, THE CONTRACTORMUST SUBMIT THE FOLLOW ING DOCUMENTS TO DEWA:·#INITIAL INSPECTION REPORT (MENTIONING THE REQUIRED SPARES ANDREQUIRED ACTIONS)·#JOB COMPLETION REPORT (INCLU DING ALL OVERHAULING ACTIONS DONE) WITHINONE WEEK OF DELIVERY·#SERVICE ENTRY APPLICATION ATTACHING THE JOB COMPLETION REPORTIMMEDIAT ELY ONCE THE REPORT IS SIGNED BY DEWA REPRESENTATIVE·#INCLUDING ALL PROPER PHOTOS, EQUIPMENT SERIAL NUMBER, AND EQUIPMENTTAGGING·#RE QUISITION FOR SPARE PARTS PLANNING BASED ON THE CURRENT CONDITIONOF THE EQUIPMENTANNEXURE I # DETAILED MANDATORY SCOPE OF WORK FOR B OOSTER PUMP OVERHAUL1.#DISMANTLING: THE CONTRACTOR SHALL DISMANTLE THE PUMP						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ACCORDING TODEWA ENGINEER#S INSTRUCTIONS. SKILLED WORKMA NSHIP AND CARE MUST BEAPPLIED DURING REMOVAL.2.#OVERHAULING: THE CONTRACTOR SHALL DISMANTLE THE ROTATING ASSEMBLY INTHEIR WORKSHOP A ND RECORD ALL FINDINGS, INCLUDING PHOTOGRAPHS OFDETERIORATED COMPONENTS. THE SHAFT MUST BE INSPECTED FOR STRAIGHTNESS,AND WORN AREAS SHOULD BE RECONDITIONED. IMPELLER, BEARINGS, MECHANICALSEAL, GLAND SLEEVE, AND WEAR RINGS MUST BE THOROUGHLY CHECKED ANDREPLACED IF NECESSARY. ALL PARTS FOUND DEFECTIVE MUST BE REPAIRED ORREPLACED, WITH AVAILABLE SPARES SUPPLIED BY DEWA. IF SPARES AREUNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SEEK APPROVAL FROMDEWA FOR ADDITIONAL COSTS. THE PUMP CASING MUST BE CLEANED AND INSPECTEDFOR DAMAGE, AND ANY NECESSARY REPAIRS MUST BE					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CARRIED OUT USINGSANDBLASTING AND FOOD-GRADE EPOXY COATING.3.#ASSEMBLY: REASSEMBLY OF THE EQUIPMENT MUST FOLLOW STANDARDPROCEDURES, ENSURING THE PROPER FIT AND CLEARANCES. THE ROTOR ASSEMBLYSHOULD BE DYNAMICALLY BALANCED P ER ISO 1940/1 STANDARDS. A DETAILEDRECORD OF ALL ACTIVITIES MUST BE MAINTAINED, AND ANY DEVIATIONS FROM SETVALUES WILL BE DETERMINED BY DEWA.4.#CONSUMABLES & ACCESSORIES: MANUFACTURING OF MECHANICAL SEAL COOLINGPIPE FITTINGS, SHAFT LOCK NUTS, LOCK WASHERS, DOWEL P INS, BEARINGSPACERS, HOLDING DOWN BOLTS, AND VARIOUS GASKETS, INCLUDING THE SUPPLYOF O-RINGS SHOULD BE PROVIDED BY THE CONTRACTOR WI TH NO ADDITIONAL COST.ANNEXURE II # OPTIONAL MACHINING WORKS1.#IMPELLER MACHINING: THIS INCLUDES GRIT BLASTING AND NON-DESTRUCTIVETE						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			STING (NDT) TO IDENTIFY CRACKS, SKIMMING THE WEAR RING AREAS, ANDFITTING NEW RINGS.2.#SHAFT MACHINING: THE SHAFT WILL UNDERGO CHROME PLATING ON BEARINGSEATING AREAS AND MECHANICAL SEAL SEATING AREAS, ALONG WITH METALREBUILDING AND STRAIGHTENING (UP TO A 4-THOU MAX IMUM BEND).3.#BEARING HOUSING MACHINING: MACHINING AND RESLEEVING OF BOTH DE ANDNDE BEARING HOUSING BORES.4.#MECHANICAL SEAL FACE: M ACHINING AND REPAIRING OF THE PUMP#S TOP ANDBOTTOM CASING HALVES AT THE MECHANICAL SEAL FACE.5.#PUMP CASINGS: SKIMMING AND GROOVING OF SUCTION AND DISCHARGE FLANGESON THE PUMP CASING.MACHINING WORKS MUST COMPLY WITH THE LATEST STANDARDS, AND PRIORAPPROVAL FROM THE DEWA ENGINEER IS REQUIRED BEFORE COMMENCING ANYMACHINING TASKS. ANY DAMAGES DONE ON ANY PROVIDED SPARES FROM					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			DEWA, THECONTRACTOR IS HELD RESPONSIBLE IN REPLACING THE DAMAGED MATERIAL AT NOADDITIONAL COST TO DEWA.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV .AE) FOR FURTHERCLARIFICATION.						
2		ITEM-00001	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP CASE WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR HATTA PH3 AVERSA PUMPSCOPE OF WORK1.#SUPPLY, M ACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP CASE WEARRING, AND INSTALL IT AS PART OF THE COMPLE TE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPL E AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTING TO VE RIFY PROPER OPERATION.4.#QUALITY AND	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT T ERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PR OVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTO R SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEW A.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
3		ITEM-00001	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP IMPELLER WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR HATTA PH3 AVERSA PUMPSCOPE OF WORK1.#SUPPL Y, MACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP IMPELLER WEARRING, AND INSTALL IT AS PART OF TH E COMPLETE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROV ED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTI NG TO VERIFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#P AYMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE C ONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL CO STTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE I NTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
4		ITEM-00001	MACHINING, SUPPLY, AND ASSEMBLY OF SHAFT SLEEVES FOR HATTA PH3 AVERSAPUMPSCOPE OF WORK1.#SUPPLY, MACHINING, AND ASSEMBLYTHE CONTRACT OR SHALL SUPPLY THE MATERIAL, MACHINE THE SHAFT SLEEVES, ANDASSEMBLE THEM ONTO THE PUMP ROTOR.2.#COMPLIANCE WITH	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SPECIFICATIONSMATER IAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CO NTRACTOR SHALL COMPLETE THE ROTOR ASSEMBLY AND PERFORM TESTING TOVERIFY PROPER FITTING, ALIGNMENT, AND OPERATION.4.#QUALITY AND ACCE PTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE O FSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			COSTTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA .BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
5		ITEM-00001	MACHINING AND REBUILDING OF SHAFT FOR HATTA PH3 AVERSA PUMPSCOPE OF WORK:1.#SHAFT REBUILDING AND MACHINING: REBUILD AND MACHINE THE PUMP SHAFTON BOTH THE DRIVE END (DE) AND NON-DRIVE END (NDE), FOCUSING ON THEMECHANICAL SEAL AND BEARING AREAS.2.#ASSEMBLY AND TESTI NG: REASSEMBLE THE PUMP AND ROTOR, FOLLOWED BYTHOROUGH TESTING TO ENSURE PROPER FUNCTIONALITY.3.#CONTRACTOR RESPONSIBILITY: THE CONT RACTOR WILL ASSUME FULLRESPONSIBILITY FOR ANY ERRORS OR MISHANDLING DURING THE PROCESS. ALLNECESSARY CORRECTIONS MUST	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
6		ITEM-00001	MODIFICATION OF MECHANICAL SEAL COOLING LINE FOR HATTA PH3 AVERSA PUMPSCOPE OF WORK:1.#FABRICATION AND MODIFICATION: FABRICATE OR MO DIFY THE MECHANICALSEAL COOLING LINE TO MEET THE SPECIFIC REQUIREMENTS OF THE PUMP.2.#ASSEMBLY AND TESTING: ASSEMBLE THE COOLING LIN E TO THE PUMP ROTORASSEMBLY, ENSURING IT ADHERES TO THE ORIGINAL DESIGN SPECIFICATIONS.TEST THE COOLING LINE THOROUGHLY TO CONFIRM T HERE ARE NO ISSUES ORLEAKS.3.#CONTRACTOR RESPONSIBILITY: THE CONTRACTOR WILL BE FULLY RESPONSIBLEFOR ANY ERRORS OR MISHANDLING DURIN G THE MODIFICATION OR ASSEMBLYPROCESS. ALL NECESSARY CORRECTIONS MUST BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			(DHRUB A.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
7		ITEM-00001	FULL BLASTING AND RECOATING OF HATTA PH3 AVERSA PUMPSPECIFICATION FOR INTERNAL COATING OF PUMPS AND VALVESTHESE PUMPS AND VALVES ARE UTILIZED IN WATER BOOSTER PUMPING STATIONS,HANDLING POTABLE WATER WITH TEMPERATURES UP TO 50°C. WHILE THE WATER ISTYPICALLY CLEAN, OCCASIONAL SAND OR SOLIDS MAY BE PRESENT IN THE STREAMFROM THE PIPELINE. THE PUMPS HAVE BEEN IN OPERATION SINCE THE STATION'SCOMMISS IONING.SCOPE OF WORK1.#COLLECTION AND TRANSPORTATION: THE CONTRACTOR IS RESPONSIBLE FORCOLLECTING THE PUMP CASING USING A SUITABLE P ICKUP OR CRANE-MOUNTEDTRUCK TO TRANSPORT IT TO DEWA'S WORKSHOP. THE CONTRACTOR MUST ENSURETHE USE OF APPROPRIATE LIFTING SLINGS/BEL	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			TS WITH SUFFICIENT LOADCAPACITY FOR SAFE LOADING AND UNLOADING.2.#SURFACE PREPARATION: BEFORE APPLYING ANY COATING, THE CONTRACTORMU ST PERFORM SURFACE PREPARATION USING SAND OR GRIT BLASTING, OR OTHERSUITABLE MECHANICAL METHODS TO REMOVE RUST AND LOOSE MATERIALS. AFTERTHE BLASTING, DEWA ENGINEERS MUST INSPECT THE SURFACE BEFORE COATING.ALL MACHINED SURFACES AND CRITICAL AREAS MUST BE ADEQUATEL Y PROTECTEDDURING SANDBLASTING TO AVOID DAMAGE. CLEAR PHOTOS MUST BE TAKEN AND BEATTACHED IN THE COMPLETION REPORT.3.#REBUILDING ERO DED/PITTED SURFACES: THE CONTRACTOR MUST RESTOREERODED SURFACES USING A SUITABLE COMPOSITE MATERIAL BEFORE APPLYING ANYCOATING. THE COMPOSITE MATERIAL MUST HAVE THE FOLLOWING PROPERTIES:O#SUITABLE FOR CONTINUOUS IMMERSION IN VARIOUS CHEMICALS						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			(E.G., FERRICCHLORIDE , HYDROCHLORIC ACID, SULFURIC ACID, SODIUM HYDROXIDE, AMMONIUMHYDROXIDE) AT 21°C.O#MUST PASS THE ASTM C868 CORROSION TEST FOR DEMINE RALIZED WATERIMMERSION AT 43°C FOR AT LEAST SIX MONTHS.O#ADHESION (ASTM D1002) GREATER THAN 183 KG/CM² (2,600 PSI).O#MEET OR EXCEED COMPRESSIVE, TENSILE, AND FLEXURAL STRENGTH STANDARDS.ENVIRONMENTAL CONDITIONS DURING SURFACE PREPARATION, APPLICATION, ANDCURING MU ST BE MONITORED TO ENSURE PROPER EXECUTION.4.#INTERNAL AND EXTERNAL COATING:O#APPLY CERAMIC-REINFORCED COMPOSITE MATERIALS FOR THE F INAL COATINGAFTER SURFACE PREPARATION AND REBUILDING.O#THE COMPOSITE MUST WITHSTAND CONTINUOUS IMMERSION IN CHEMICALS ANDPASS THE AS TM B117 SALT FOG AND ASTM G8 CATHODIC DISBANDMENT TESTS.O#THE COATING MUST BE 800-1000 MICRONS THICK AND FINISHED WITH					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ASMOOTH, ABRA SION-RESISTANT GLASS-LIKE SURFACE.O#THE COMPOSITE MATERIAL MUST BE AUTHORIZED FOR USDA INCIDENTAL FOODCONTACT APPLICATIONS AND HOLD POTABLE WATER CERTIFICATION FROM WRAS OREQUIVALENT AUTHORITIES.O#EXTERNAL COATING SHOULD BE AN EPOXY COATING, 300-400 MICRONS THICK, IN BLUE COLOR FOR BOTH PUMPS AND VALVES.5.#WARRANTY: THE SUPPLIER MUST PROVIDE A 24-MONTH SERVICE WARRANTYAGAINST ANY DEFECTS IN THE COATING. IF THE COATING FAILS WITHIN THISPERIOD, THE SUPPLIER WILL RECOAT THE EQUIPMENT FREE OF CHARGE.6.#METHOD STATEMENT: THE SUP PLIER MUST SUBMIT A DETAILED METHODSTATEMENT FOR THE COATING PROCESS, INCLUDING MATERIAL SPECIFICATIONS,FOR REVIEW AND APPROVAL.7.#I NSPECTION: PRIOR TO DELIVERY, THE COATING WORK MUST BE INSPECTED BYDEWA ENGINEERS						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AT THE SUPPLIER'S WORKSHOP FOR FINAL ACCEPTANCE. T HECONTRACTOR MUST PROVIDE ALL NECESSARY INSPECTION TOOLS.8.#REPORTS AND DOCUMENTATION: UPON DELIVERY, THE CONTRACTOR MUST SUBMITTHE FOLLOWING:O#MATERIAL DATA SHEETS BEFORE AND AFTER COATING.O#WRAS CERTIFICATION FOR COATING MATERIALS.O#ALL RELEVANT TEST REPORTS.O#P ROPER COMPLETION REPORT INCLUDING THE INTERNAL CONDITION BEFORE ANDAFTER THE BLASTING AND THE COATING.KINDLY CONTACT MR. DHRUBA (DHR UBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
8		ITEM-00002	COMPLETE OVERHAULING OF BOOSTER PUMP FOR DIP PUMPING STATION. PUMPDETAILS: CLYDE UNION PUMP MODEL: DVL-350X300, HEAD-140M, FLOW-263L /S,RPM-1475, 630KW.SCOPE OF WORKTHE FOLLOWING OUTLINES THE MANDATORY AND OPTIONAL SCOPE OF WORK FOR THEOVERHAUL	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OF BOOSTER PUMPS AND THEIR ACCESSORIES AT THE BOOSTER PUMPINGSTATION.1.0 MANDATORY SCOPE OF WORK:A) THE CONTRACTOR IS RESPONSIBLE FOR TRANSPORTING THE P UMP ASSEMBLY TOAND FROM THE DEWA SITE TO THEIR WORKSHOP. DEWA WILL NOT PROVIDETRANSPORTATION. FOR LOADING AND UNLOADING, THE CONTRAC TOR MAY USE DEWA#SOVERHEAD CRANE AT THE PUMPING STATION, WITH PROPER COORDINATION WITHDEWA REPRESENTATIVES. B) REPLACEMENT OF THE ME CHANICAL SEAL, COUPLINGBUSH RENEWAL, GLAND PACKING RENEWAL, AND BEARING REPLACEMENT ASREQUIRED. C) OVERHAULING OF THE PUMP (REFER TO ANNEXURE I FOR MANDATORYAND ANNEXURE II FOR OPTIONAL WORK). D) EXTERNAL PAINTING OF THE PUMP. E)RECTIFICATION OF ANY ISSUES THAT AR ISE AFTER INSTALLATION/LOAD TESTING.THIS SHALL BE DONE ON SITE IF POSSIBLE, AND IF NOT,						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THE CONTRACTOR ISRESPONSIBLE IN COLLECTING T HE PUMP AND MOVED IT BACK TO THEIR FACILITY.F) IF ANY PART IS FOUND DEFECTIVE, THE CONTRACTOR IS RESPONSIBLE FORREPAIRING OR REPLACI NG IT. DEWA WILL PROVIDE AVAILABLE SPARES. IF ANYSPARE PARTS ARE UNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SUBMITTHE COST FO R DEWA APPROVAL BEFORE PLACING AN ORDER. G) ONCE THE PUMP ISFULLY ASSEMBLED, THE PUMP MUST BE PRESSURE HYDRO TESTED IN THECONTRACTOR FACILITY TO MAKE SURE THE PUMP IS WELL ASSEMBLED AND THATTHERE ARE NO LEAKS.2.0 REQUIREMENTS PRIOR TO QUOTATION SUBMISSION:A) THE C ONTRACTOR MUST VISIT THE SITE TO FAMILIARIZE THEMSELVES WITH THESCOPE OF WORK AND POTENTIAL COMPLEXITIES BEFORE SUBMITTING A QUOTATI ON.B) DEWA WILL NOT ACCEPT ANY CLAIMS FOR						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ADDITIONAL CHARGES BEYOND THEAGREED RATES OR PRICES DURING OR AFTER THE EXECUTION OF THE W ORK. C) THECONTRACTOR WILL BE PROVIDED WITH AN EQUIPMENT SHUTDOWN SCHEDULE INCOORDINATION WITH THE OPERATIONS & MAINTENANCE DEPARTME NT OF THE WATERDIVISION. D) A TIME SCHEDULE OR BAR CHART SHOWING EACH ACTIVITY MUST BESUBMITTED. E) UPON COMPLETION, AN INSPECTION C HECKLIST AND QUALITYPROCEDURE DOCUMENTATION, WHERE APPLICABLE, MUST BE SUBMITTED. F) THECONTRACTOR IS RESPONSIBLE FOR SITE SUPERVISI ON, COORDINATION OF FIELDACTIVITIES, AND THE SUPPLY OF REQUIRED TECHNICIANS, TOOLS, EQUIPMENT,AND RESOURCES NECESSARY TO EXECUTE THE CONTRACT.3.0 TAKEOVER:UPON COMPLETION OF ALL WORK WITHIN THE SCOPE OF THE CONTRACT, THECONTRACTOR MUST NOTIFY DEWA IN WRITING. A CE						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			RTIFICATE OF COMPLETION WILLBE ISSUED AFTER A FINAL INSPECTION, CONFIRMING THAT THE WORK HAS BEENACCEPTED AND TAKEN OVER BY DEWA FOL LOWING THE NECESSARY CONDITIONMONITORING CHECKS.4.0 WARRANTY:A) ALL WORK WILL CARRY A WARRANTY OF 8,000 HOURS OF OPERATION OR ONEYEA R, WHICHEVER COMES FIRST. B) THE WARRANTY WILL TAKE EFFECT FROM THEDATE OF DEWA'S OFFICIAL TAKEOVER OF THE COMPLETED JOB. C) IF ANY DEFECTSARE IDENTIFIED DURING THE WARRANTY PERIOD, THE CONTRACTOR MUST RECTIFYTHEM WITHIN THE TIMEFRAME SET BY DEWA WITHOUT ADDITIONA L COST ORCOMPENSATION.5.0 DOCUMENTATION:UPON SATISFACTORY COMPLETION OF THE WORK AND HANDOVER, THE CONTRACTORMUST SUBMIT THE FOLLOWI NG DOCUMENTS TO DEWA:·#INITIAL INSPECTION REPORT (MENTIONING THE REQUIRED SPARES ANDREQUIRED ACTIONS)·#JOB COMPLETION						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			REPORT (INCLUD ING ALL OVERHAULING ACTIONS DONE) WITHINONE WEEK OF DELIVERY·#SERVICE ENTRY APPLICATION ATTACHING THE JOB COMPLETION REPORTIMMEDIATE LY ONCE THE REPORT IS SIGNED BY DEWA REPRESENTATIVE·#INCLUDING ALL PROPER PHOTOS, EQUIPMENT SERIAL NUMBER, AND EQUIPMENTTAGGING·#REQ UISITION FOR SPARE PARTS PLANNING BASED ON THE CURRENT CONDITIONOF THE EQUIPMENTANNEXURE I # DETAILED MANDATORY SCOPE OF WORK FOR BO OSTER PUMP OVERHAUL1.#DISMANTLING: THE CONTRACTOR SHALL DISMANTLE THE PUMP ACCORDING TODEWA ENGINEER#S INSTRUCTIONS. SKILLED WORKMAN SHIP AND CARE MUST BEAPPLIED DURING REMOVAL.2.#OVERHAULING: THE CONTRACTOR SHALL DISMANTLE THE ROTATING ASSEMBLY INTHEIR WORKSHOP AN D RECORD ALL FINDINGS, INCLUDING PHOTOGRAPHS OFDETERIORATED COMPONENTS.						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THE SHAFT MUST BE INSPECTED FOR STRAIGHTNESS,AND WORN AREAS SHOULD BE RECONDITIONED. IMPELLER, BEARINGS, MECHANICALSEAL, GLAND SLEEVE, AND WEAR RINGS MUST BE THOROUGHLY CHECKED ANDREPLACED IF NECESSARY. ALL PARTS FOUND DEFECTIVE MUST BE REPAIRED ORREPLACED, WITH AVAILABLE SPARES SUPPLIED BY DEWA. IF SPARES AREUNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SEEK APPROVAL FROMDEWA FOR ADDITIONAL COSTS. THE PUMP CASING MUST BE CLEANED AND INSPECTEDFOR D AMAGE, AND ANY NECESSARY REPAIRS MUST BE CARRIED OUT USINGSANDBLASTING AND FOOD-GRADE EPOXY COATING.3.#ASSEMBLY: REASSEMBLY OF THE E QUIPMENT MUST FOLLOW STANDARDPROCEDURES, ENSURING THE PROPER FIT AND CLEARANCES. THE ROTOR ASSEMBLYSHOULD BE DYNAMICALLY BALANCED PE					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			R ISO 1940/1 STANDARDS. A DETAILEDRECORD OF ALL ACTIVITIES MUST BE MAINTAINED, AND ANY DEVIATIONS FROM SETVALUES WILL BE DETERMINED BY DEWA.4.#CONSUMABLES & ACCESSORIES: MANUFACTURING OF MECHANICAL SEAL COOLINGPIPE FITTINGS, SHAFT LOCK NUTS, LOCK WASHERS, DOWEL PI NS, BEARINGSPACERS, HOLDING DOWN BOLTS, AND VARIOUS GASKETS, INCLUDING THE SUPPLYOF O-RINGS SHOULD BE PROVIDED BY THE CONTRACTOR WIT H NO ADDITIONAL COST.ANNEXURE II # OPTIONAL MACHINING WORKS1.#IMPELLER MACHINING: THIS INCLUDES GRIT BLASTING AND NON-DESTRUCTIVETES TING (NDT) TO IDENTIFY CRACKS, SKIMMING THE WEAR RING AREAS, ANDFITTING NEW RINGS.2.#SHAFT MACHINING: THE SHAFT WILL UNDERGO CHROME PLATING ON BEARINGSEATING AREAS AND MECHANICAL SEAL SEATING AREAS, ALONG WITH METALREBUILDING AND STRAIGHTENING (UP TO A						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			4-THOU MAXI MUM BEND).3.#BEARING HOUSING MACHINING: MACHINING AND RESLEEVING OF BOTH DE ANDNDE BEARING HOUSING BORES.4.#MECHANICAL SEAL FACE: MA CHINING AND REPAIRING OF THE PUMP#S TOP ANDBOTTOM CASING HALVES AT THE MECHANICAL SEAL FACE.5.#PUMP CASINGS: SKIMMING AND GROOVING O F SUCTION AND DISCHARGE FLANGESON THE PUMP CASING.MACHINING WORKS MUST COMPLY WITH THE LATEST STANDARDS, AND PRIORAPPROVAL FROM THE DEWA ENGINEER IS REQUIRED BEFORE COMMENCING ANYMACHINING TASKS. ANY DAMAGES DONE ON ANY PROVIDED SPARES FROM DEWA, THECONTRACTOR IS HELD RESPONSIBLE IN REPLACING THE DAMAGED MATERIAL AT NOADDITIONAL COST TO DEWA.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV. AE) FOR FURTHERCLARIFICATION.						
9		ITEM-00002	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CASE WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR DIP CLYDE UNION PUMPSCOPE OF WORK1.#SUPPLY, MA CHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP CASE WEARRING, AND INSTALL IT AS PART OF THE COMPLET E PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTING TO VER IFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TE RMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PRO VIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEWA .8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED S ERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
10		ITEM-00002	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP IMPELLER WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR DIP CLYDE UNION PUMPSCOPE OF WORK1.#SUPPLY , MACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP IMPELLER WEARRING, AND INSTALL IT AS	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PART OF THE COMPLETE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVE D SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTIN G TO VERIFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PA YMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR S HALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CO NTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026
REQ No : 1032605314
REQ TITLE : Complete pump overhauling and
DELIVERY LOCATION
CLOSING DATE : 06.11.2026
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COS TTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE IN TENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
11		ITEM-00002	MACHINING, SUPPLY, AND ASSEMBLY OF SHAFT SLEEVES FOR DIP CLYDE UNIONPUMPSCOPE OF WORK1.#SUPPLY, MACHINING, AND ASSEMBLYTHE CONTRACTO R SHALL SUPPLY THE MATERIAL, MACHINE THE SHAFT SLEEVES, ANDASSEMBLE THEM ONTO THE PUMP ROTOR.2.#COMPLIANCE WITH SPECIFICATIONSMATERI AL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CON TRACTOR SHALL COMPLETE THE ROTOR ASSEMBLY AND PERFORM TESTING TOVERIFY	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PROPER FITTING, ALIGNMENT, AND OPERATION.4.#QUALITY AND ACCEP TANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OF SUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, M ACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL P ROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA. BANERJEE@DEWA.GOV.AE) FOR					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FURTHERCLARIFICATION.						
12		ITEM-00002	MACHINING AND REBUILDING OF SHAFT FOR DIP CLYDE UNION PUMPSCOPE OF WORK:1.#SHAFT REBUILDING AND MACHINING: REBUILD AND MACHINE THE P UMP SHAFTON BOTH THE DRIVE END (DE) AND NON-DRIVE END (NDE), FOCUSING ON THEMECHANICAL SEAL AND BEARING AREAS.2.#ASSEMBLY AND TESTIN G: REASSEMBLE THE PUMP AND ROTOR, FOLLOWED BYTHOROUGH TESTING TO ENSURE PROPER FUNCTIONALITY.3.#CONTRACTOR RESPONSIBILITY: THE CONTR ACTOR WILL ASSUME FULLRESPONSIBILITY FOR ANY ERRORS OR MISHANDLING DURING THE PROCESS. ALLNECESSARY CORRECTIONS MUST BE MADE AT NO A DDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.	1	EA				
13		ITEM-00002	MODIFICATION OF MECHANICAL SEAL COOLING LINE FOR DIP CLYDE UNION PUMPSCOPE OF WORK:1.#FABRICATION AND MODIFICATION:	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FABRICATE OR MOD IFY THE MECHANICALSEAL COOLING LINE TO MEET THE SPECIFIC REQUIREMENTS OF THE PUMP.2.#ASSEMBLY AND TESTING: ASSEMBLE THE COOLING LINE TO THE PUMP ROTORASSEMBLY, ENSURING IT ADHERES TO THE ORIGINAL DESIGN SPECIFICATIONS.TEST THE COOLING LINE THOROUGHLY TO CONFIRM TH ERE ARE NO ISSUES ORLEAKS.3.#CONTRACTOR RESPONSIBILITY: THE CONTRACTOR WILL BE FULLY RESPONSIBLEFOR ANY ERRORS OR MISHANDLING DURING THE MODIFICATION OR ASSEMBLYPROCESS. ALL NECESSARY CORRECTIONS MUST BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA .BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
14		ITEM-00002	FULL BLASTING AND RECOATING OF DIP CLYDE UNION PUMPSPECIFICATION FOR INTERNAL COATING OF PUMPS AND VALVESTHESE PUMPS AND VALVES ARE	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			UTILIZED IN WATER BOOSTER PUMPING STATIONS,HANDLING POTABLE WATER WITH TEMPERATURES UP TO 50°C. WHILE THE WATER ISTYPICALLY CLEAN, O CCASIONAL SAND OR SOLIDS MAY BE PRESENT IN THE STREAMFROM THE PIPELINE. THE PUMPS HAVE BEEN IN OPERATION SINCE THE STATION'SCOMMISSI ONING.SCOPE OF WORK1.#COLLECTION AND TRANSPORTATION: THE CONTRACTOR IS RESPONSIBLE FORCOLLECTING THE PUMP CASING USING A SUITABLE PI CKUP OR CRANE-MOUNTEDTRUCK TO TRANSPORT IT TO DEWA'S WORKSHOP. THE CONTRACTOR MUST ENSURETHE USE OF APPROPRIATE LIFTING SLINGS/BELT S WITH SUFFICIENT LOADCAPACITY FOR SAFE LOADING AND UNLOADING.2.#SURFACE PREPARATION: BEFORE APPLYING ANY COATING, THE CONTRACTORMUS T PERFORM SURFACE PREPARATION USING SAND OR GRIT BLASTING, OR OTHERSUITABLE MECHANICAL METHODS TO REMOVE RUST AND					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			LOOSE MATERIALS. A FTERTHE BLASTING, DEWA ENGINEERS MUST INSPECT THE SURFACE BEFORE COATING.ALL MACHINED SURFACES AND CRITICAL AREAS MUST BE ADEQUATELY PROTECTEDDURING SANDBLASTING TO AVOID DAMAGE. CLEAR PHOTOS MUST BE TAKEN AND BEATTACHED IN THE COMPLETION REPORT.3.#REBUILDING EROD ED/PITTED SURFACES: THE CONTRACTOR MUST RESTOREERODED SURFACES USING A SUITABLE COMPOSITE MATERIAL BEFORE APPLYING ANYCOATING. THE C OMPOSITE MATERIAL MUST HAVE THE FOLLOWING PROPERTIES:O#SUITABLE FOR CONTINUOUS IMMERSION IN VARIOUS CHEMICALS (E.G., FERRICCHLORIDE, HYDROCHLORIC ACID, SULFURIC ACID, SODIUM HYDROXIDE, AMMONIUMHYDROXIDE) AT 21°C.O#MUST PASS THE ASTM C868 CORROSION TEST FOR DEMINER ALIZED WATERIMMERSION AT 43°C FOR AT LEAST SIX MONTHS.O#ADHESION (ASTM D1002) GREATER						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THAN 183 KG/CM² (2,600 PSI).O#MEET OR EXCEED C OMPRESSIVE, TENSILE, AND FLEXURAL STRENGTH STANDARDS.ENVIRONMENTAL CONDITIONS DURING SURFACE PREPARATION, APPLICATION, ANDCURING MUS T BE MONITORED TO ENSURE PROPER EXECUTION.4.#INTERNAL AND EXTERNAL COATING:O#APPLY CERAMIC-REINFORCED COMPOSITE MATERIALS FOR THE FI NAL COATINGAFTER SURFACE PREPARATION AND REBUILDING.O#THE COMPOSITE MUST WITHSTAND CONTINUOUS IMMERSION IN CHEMICALS ANDPASS THE AST M B117 SALT FOG AND ASTM G8 CATHODIC DISBANDMENT TESTS.O#THE COATING MUST BE 800-1000 MICRONS THICK AND FINISHED WITH ASMOOTH, ABRAS ION-RESISTANT GLASS-LIKE SURFACE.O#THE COMPOSITE MATERIAL MUST BE AUTHORIZED FOR USDA INCIDENTAL FOODCONTACT APPLICATIONS AND HOLD P OTABLE WATER CERTIFICATION FROM WRAS						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OREQUIVALENT AUTHORITIES.O#EXTERNAL COATING SHOULD BE AN EPOXY COATING, 300-400 MICRONS THICK,I N BLUE COLOR FOR BOTH PUMPS AND VALVES.5.#WARRANTY: THE SUPPLIER MUST PROVIDE A 24-MONTH SERVICE WARRANTYAGAINST ANY DEFECTS IN THE COATING. IF THE COATING FAILS WITHIN THISPERIOD, THE SUPPLIER WILL RECOAT THE EQUIPMENT FREE OF CHARGE.6.#METHOD STATEMENT: THE SUPP LIER MUST SUBMIT A DETAILED METHODSTATEMENT FOR THE COATING PROCESS, INCLUDING MATERIAL SPECIFICATIONS,FOR REVIEW AND APPROVAL.7.#IN SPECTION: PRIOR TO DELIVERY, THE COATING WORK MUST BE INSPECTED BYDEWA ENGINEERS AT THE SUPPLIER'S WORKSHOP FOR FINAL ACCEPTANCE. TH ECONTRACTOR MUST PROVIDE ALL NECESSARY INSPECTION TOOLS.8.#REPORTS AND DOCUMENTATION: UPON DELIVERY, THE CONTRACTOR MUST SUBMITTHE F					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026
REQ No : 1032605314
REQ TITLE : Complete pump overhauling and
DELIVERY LOCATION
CLOSING DATE : 06.11.2026
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OLLOWING:O#MATERIAL DATA SHEETS BEFORE AND AFTER COATING.O#WRAS CERTIFICATION FOR COATING MATERIALS.O#ALL RELEVANT TEST REPORTS.O#PR OPER COMPLETION REPORT INCLUDING THE INTERNAL CONDITION BEFORE ANDAFTER THE BLASTING AND THE COATING.KINDLY CONTACT MR. DHRUBA (DHRU BA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
15		ITEM-00003	COMPLETE OVERHAULING OF BOOSTER PUMP FOR MUSHRIF PUMPING STATION. PUMPDETAILS: AVERSA PUMP MODEL: DVL-350X300, HEAD-140M, FLOW-263L/ S,RPM-1475, 630KW.SCOPE OF WORKTHE FOLLOWING OUTLINES THE MANDATORY AND OPTIONAL SCOPE OF WORK FOR THEOVERHAUL OF BOOSTER PUMPS AND THEIR ACCESSORIES AT THE BOOSTER PUMPINGSTATION.1.0 MANDATORY SCOPE OF WORK:A) THE CONTRACTOR IS RESPONSIBLE FOR TRANSPORTING THE PU MP ASSEMBLY TOAND FROM THE DEWA SITE TO	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THEIR WORKSHOP. DEWA WILL NOT PROVIDETRANSPORTATION. FOR LOADING AND UNLOADING, THE CONTRACT OR MAY USE DEWA#SOVERHEAD CRANE AT THE PUMPING STATION, WITH PROPER COORDINATION WITHDEWA REPRESENTATIVES. B) REPLACEMENT OF THE MEC HANICAL SEAL, COUPLINGBUSH RENEWAL, GLAND PACKING RENEWAL, AND BEARING REPLACEMENT ASREQUIRED. C) OVERHAULING OF THE PUMP (REFER TO ANNEXURE I FOR MANDATORYAND ANNEXURE II FOR OPTIONAL WORK). D) EXTERNAL PAINTING OF THE PUMP. E)RECTIFICATION OF ANY ISSUES THAT ARI SE AFTER INSTALLATION/LOAD TESTING.THIS SHALL BE DONE ON SITE IF POSSIBLE, AND IF NOT, THE CONTRACTOR ISRESPONSIBLE IN COLLECTING TH E PUMP AND MOVED IT BACK TO THEIR FACILITY.F) IF ANY PART IS FOUND DEFECTIVE, THE CONTRACTOR IS RESPONSIBLE FORREPAIRING OR REPLACIN					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			G IT. DEWA WILL PROVIDE AVAILABLE SPARES. IF ANYSPARE PARTS ARE UNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SUBMITTHE COST FOR DEWA APPROVAL BEFORE PLACING AN ORDER. G) ONCE THE PUMP ISFULLY ASSEMBLED, THE PUMP MUST BE PRESSURE HYDRO TESTED IN THECONTRACTOR FACILITY TO MAKE SURE THE PUMP IS WELL ASSEMBLED AND THATTHERE ARE NO LEAKS.2.0 REQUIREMENTS PRIOR TO QUOTATION SUBMISSION:A) THE CO NTRACTOR MUST VISIT THE SITE TO FAMILIARIZE THEMSELVES WITH THESCOPE OF WORK AND POTENTIAL COMPLEXITIES BEFORE SUBMITTING A QUOTATIO N.B) DEWA WILL NOT ACCEPT ANY CLAIMS FOR ADDITIONAL CHARGES BEYOND THEAGREED RATES OR PRICES DURING OR AFTER THE EXECUTION OF THE WO RK. C) THECONTRACTOR WILL BE PROVIDED WITH AN EQUIPMENT SHUTDOWN SCHEDULE INCOORDINATION WITH THE OPERATIONS &						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			MAINTENANCE DEPARTMEN T OF THE WATERDIVISION. D) A TIME SCHEDULE OR BAR CHART SHOWING EACH ACTIVITY MUST BESUBMITTED. E) UPON COMPLETION, AN INSPECTION CH ECKLIST AND QUALITYPROCEDURE DOCUMENTATION, WHERE APPLICABLE, MUST BE SUBMITTED. F) THECONTRACTOR IS RESPONSIBLE FOR SITE SUPERVISIO N, COORDINATION OF FIELDACTIVITIES, AND THE SUPPLY OF REQUIRED TECHNICIANS, TOOLS, EQUIPMENT,AND RESOURCES NECESSARY TO EXECUTE THE CONTRACT.3.0 TAKEOVER:UPON COMPLETION OF ALL WORK WITHIN THE SCOPE OF THE CONTRACT, THECONTRACTOR MUST NOTIFY DEWA IN WRITING. A CER TIFICATE OF COMPLETION WILLBE ISSUED AFTER A FINAL INSPECTION, CONFIRMING THAT THE WORK HAS BEENACCEPTED AND TAKEN OVER BY DEWA FOLL OWING THE NECESSARY CONDITIONMONITORING CHECKS.4.0 WARRANTY:A) ALL WORK WILL CARRY					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			A WARRANTY OF 8,000 HOURS OF OPERATION OR ONEYEAR , WHICHEVER COMES FIRST. B) THE WARRANTY WILL TAKE EFFECT FROM THEDATE OF DEWA'S OFFICIAL TAKEOVER OF THE COMPLETED JOB. C) IF ANY D EFECTSARE IDENTIFIED DURING THE WARRANTY PERIOD, THE CONTRACTOR MUST RECTIFYTHEM WITHIN THE TIMEFRAME SET BY DEWA WITHOUT ADDITIONAL COST ORCOMPENSATION.5.0 DOCUMENTATION:UPON SATISFACTORY COMPLETION OF THE WORK AND HANDOVER, THE CONTRACTORMUST SUBMIT THE FOLLOWIN G DOCUMENTS TO DEWA:·#INITIAL INSPECTION REPORT (MENTIONING THE REQUIRED SPARES ANDREQUIRED ACTIONS)·#JOB COMPLETION REPORT (INCLUDI NG ALL OVERHAULING ACTIONS DONE) WITHINONE WEEK OF DELIVERY·#SERVICE ENTRY APPLICATION ATTACHING THE JOB COMPLETION REPORTIMMEDIATEL Y ONCE THE REPORT IS SIGNED BY DEWA						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			REPRESENTATIVE·#INCLUDING ALL PROPER PHOTOS, EQUIPMENT SERIAL NUMBER, AND EQUIPMENTTAGGING·#REQU ISITION FOR SPARE PARTS PLANNING BASED ON THE CURRENT CONDITIONOF THE EQUIPMENTANNEXURE I # DETAILED MANDATORY SCOPE OF WORK FOR BOO STER PUMP OVERHAUL1.#DISMANTLING: THE CONTRACTOR SHALL DISMANTLE THE PUMP ACCORDING TODEWA ENGINEER#S INSTRUCTIONS. SKILLED WORKMANS HIP AND CARE MUST BEAPPLIED DURING REMOVAL.2.#OVERHAULING: THE CONTRACTOR SHALL DISMANTLE THE ROTATING ASSEMBLY INTHEIR WORKSHOP AND RECORD ALL FINDINGS, INCLUDING PHOTOGRAPHS OFDETERIORATED COMPONENTS. THE SHAFT MUST BE INSPECTED FOR STRAIGHTNESS,AND WORN AREAS S HOULD BE RECONDITIONED. IMPELLER, BEARINGS, MECHANICALSEAL, GLAND SLEEVE, AND WEAR RINGS MUST BE THOROUGHLY CHECKED ANDREPLACED IF N						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ECESSARY. ALL PARTS FOUND DEFECTIVE MUST BE REPAIRED ORREPLACED, WITH AVAILABLE SPARES SUPPLIED BY DEWA. IF SPARES AREUNAVAILABLE, T HE CONTRACTOR MUST ARRANGE THEM AND SEEK APPROVAL FROMDEWA FOR ADDITIONAL COSTS. THE PUMP CASING MUST BE CLEANED AND INSPECTEDFOR DA MAGE, AND ANY NECESSARY REPAIRS MUST BE CARRIED OUT USINGSANDBLASTING AND FOOD-GRADE EPOXY COATING.3.#ASSEMBLY: REASSEMBLY OF THE EQ UIPMENT MUST FOLLOW STANDARDPROCEDURES, ENSURING THE PROPER FIT AND CLEARANCES. THE ROTOR ASSEMBLYSHOULD BE DYNAMICALLY BALANCED PER ISO 1940/1 STANDARDS. A DETAILEDRECORD OF ALL ACTIVITIES MUST BE MAINTAINED, AND ANY DEVIATIONS FROM SETVALUES WILL BE DETERMINED B Y DEWA.4.#CONSUMABLES & ACCESSORIES: MANUFACTURING OF MECHANICAL SEAL COOLINGPIPE FITTINGS, SHAFT LOCK NUTS, LOCK						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			WASHERS, DOWEL PIN S, BEARINGSPACERS, HOLDING DOWN BOLTS, AND VARIOUS GASKETS, INCLUDING THE SUPPLYOF O-RINGS SHOULD BE PROVIDED BY THE CONTRACTOR WITH NO ADDITIONAL COST.ANNEXURE II # OPTIONAL MACHINING WORKS1.#IMPELLER MACHINING: THIS INCLUDES GRIT BLASTING AND NON-DESTRUCTIVETEST ING (NDT) TO IDENTIFY CRACKS, SKIMMING THE WEAR RING AREAS, ANDFITTING NEW RINGS.2.#SHAFT MACHINING: THE SHAFT WILL UNDERGO CHROME P LATING ON BEARINGSEATING AREAS AND MECHANICAL SEAL SEATING AREAS, ALONG WITH METALREBUILDING AND STRAIGHTENING (UP TO A 4-THOU MAXIM UM BEND).3.#BEARING HOUSING MACHINING: MACHINING AND RESLEEVING OF BOTH DE ANDNDE BEARING HOUSING BORES.4.#MECHANICAL SEAL FACE: MAC HINING AND REPAIRING OF THE PUMP#S TOP ANDBOTTOM CASING HALVES AT THE MECHANICAL					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SEAL FACE.5.#PUMP CASINGS: SKIMMING AND GROOVING OF SUCTION AND DISCHARGE FLANGESON THE PUMP CASING.MACHINING WORKS MUST COMPLY WITH THE LATEST STANDARDS, AND PRIORAPPROVAL FROM THE D EWA ENGINEER IS REQUIRED BEFORE COMMENCING ANYMACHINING TASKS. ANY DAMAGES DONE ON ANY PROVIDED SPARES FROM DEWA, THECONTRACTOR IS H ELD RESPONSIBLE IN REPLACING THE DAMAGED MATERIAL AT NOADDITIONAL COST TO DEWA.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.A E) FOR FURTHERCLARIFICATION.						
16		ITEM-00003	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP CASE WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR MUSHRIF AVERSA PUMPSCOPE OF WORK1.#SUPPLY, MAC HINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP CASE WEARRING, AND INSTALL IT AS PART OF THE COMPLETE	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTING TO VERI FY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TER MSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROV IDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			COSTTO DEWA. 8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SE RVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
17		ITEM-00003	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP IMPELLER WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR MUSHRIF AVERSA PUMPSCOPE OF WORK1.#SUPPLY, MACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP IMPELLER WEARRING, AND INSTALL IT AS PART OF THE COMPLETE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ASSEMBLY AND PERFORM ROTOR/PUMPTESTING TO VERIFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAY MENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SH ALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CON TRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COST TO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INT ENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FURTHERCLARIFICATION.						
18		ITEM-00003	MACHINING, SUPPLY, AND ASSEMBLY OF SHAFT SLEEVES FOR MUSHRIF AVERSA PUMPSCOPE OF WORK1.#SUPPLY, MACHINING, AND ASSEMBLYTHE CONTRACTO R SHALL SUPPLY THE MATERIAL, MACHINE THE SHAFT SLEEVES, ANDASSEMBLE THEM ONTO THE PUMP ROTOR.2.#COMPLIANCE WITH SPECIFICATIONSMATERI AL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CON TRACTOR SHALL COMPLETE THE ROTOR ASSEMBLY AND PERFORM TESTING TOVERIFY PROPER FITTING, ALIGNMENT, AND OPERATION.4.#QUALITY AND ACCEP TANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OF SUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, M ACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL P ROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA. BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
19		ITEM-00003	MACHINING AND REBUILDING OF SHAFT FOR MUSHRIF AVERSA PUMPSCOPE OF WORK:1.#SHAFT REBUILDING AND MACHINING: REBUILD AND MACHINE THE PU MP SHAFTON BOTH THE DRIVE END (DE) AND NON-DRIVE END (NDE), FOCUSING ON THEMECHANICAL SEAL AND BEARING	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026
REQ No : 1032605314
REQ TITLE : Complete pump overhauling and
DELIVERY LOCATION
CLOSING DATE : 06.11.2026
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AREAS.2.#ASSEMBLY AND TESTING : REASSEMBLE THE PUMP AND ROTOR, FOLLOWED BYTHOROUGH TESTING TO ENSURE PROPER FUNCTIONALITY.3.#CONTRACTOR RESPONSIBILITY: THE CONTRA CTOR WILL ASSUME FULLRESPONSIBILITY FOR ANY ERRORS OR MISHANDLING DURING THE PROCESS. ALLNECESSARY CORRECTIONS MUST BE MADE AT NO AD DITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
20		ITEM-00003	MODIFICATION OF MECHANICAL SEAL COOLING LINE FOR MUSHRIF AVERSA PUMPSCOPE OF WORK:1.#FABRICATION AND MODIFICATION: FABRICATE OR MODI FY THE MECHANICALSEAL COOLING LINE TO MEET THE SPECIFIC REQUIREMENTS OF THE PUMP.2.#ASSEMBLY AND TESTING: ASSEMBLE THE COOLING LINE TO THE PUMP ROTORASSEMBLY, ENSURING IT ADHERES TO THE ORIGINAL DESIGN SPECIFICATIONS.TEST THE COOLING LINE	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THOROUGHLY TO CONFIRM THE RE ARE NO ISSUES ORLEAKS.3.#CONTRACTOR RESPONSIBILITY: THE CONTRACTOR WILL BE FULLY RESPONSIBLEFOR ANY ERRORS OR MISHANDLING DURING THE MODIFICATION OR ASSEMBLYPROCESS. ALL NECESSARY CORRECTIONS MUST BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA. BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
21		ITEM-00003	FULL BLASTING AND RECOATING OF MUSHRIF AVERSA PUMPSPECIFICATION FOR INTERNAL COATING OF PUMPS AND VALVESTHESE PUMPS AND VALVES ARE U TILIZED IN WATER BOOSTER PUMPING STATIONS,HANDLING POTABLE WATER WITH TEMPERATURES UP TO 50°C. WHILE THE WATER ISTYPICALLY CLEAN, OC CASIONAL SAND OR SOLIDS MAY BE PRESENT IN THE STREAMFROM THE PIPELINE. THE PUMPS HAVE BEEN IN OPERATION SINCE THE STATION'SCOMMISSIO	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			NING.SCOPE OF WORK1.#COLLECTION AND TRANSPORTATION: THE CONTRACTOR IS RESPONSIBLE FORCOLLECTING THE PUMP CASING USING A SUITABLE PIC KUP OR CRANE-MOUNTEDTRUCK TO TRANSPORT IT TO DEWA'S WORKSHOP. THE CONTRACTOR MUST ENSURETHE USE OF APPROPRIATE LIFTING SLINGS/BELTS WITH SUFFICIENT LOADCAPACITY FOR SAFE LOADING AND UNLOADING.2.#SURFACE PREPARATION: BEFORE APPLYING ANY COATING, THE CONTRACTORMUST PERFORM SURFACE PREPARATION USING SAND OR GRIT BLASTING, OR OTHERSUITABLE MECHANICAL METHODS TO REMOVE RUST AND LOOSE MATERIALS. AF TERTHE BLASTING, DEWA ENGINEERS MUST INSPECT THE SURFACE BEFORE COATING.ALL MACHINED SURFACES AND CRITICAL AREAS MUST BE ADEQUATELY PROTECTEDDURING SANDBLASTING TO AVOID DAMAGE. CLEAR PHOTOS MUST BE TAKEN AND BEATTACHED IN THE COMPLETION						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			REPORT.3.#REBUILDING ERODE D/PITTED SURFACES: THE CONTRACTOR MUST RESTOREERODED SURFACES USING A SUITABLE COMPOSITE MATERIAL BEFORE APPLYING ANYCOATING. THE CO MPOSITE MATERIAL MUST HAVE THE FOLLOWING PROPERTIES:O#SUITABLE FOR CONTINUOUS IMMERSION IN VARIOUS CHEMICALS (E.G., FERRICCHLORIDE, HYDROCHLORIC ACID, SULFURIC ACID, SODIUM HYDROXIDE, AMMONIUMHYDROXIDE) AT 21°C.O#MUST PASS THE ASTM C868 CORROSION TEST FOR DEMINERA LIZED WATERIMMERSION AT 43°C FOR AT LEAST SIX MONTHS.O#ADHESION (ASTM D1002) GREATER THAN 183 KG/CM² (2,600 PSI).O#MEET OR EXCEED CO MPRESSIVE, TENSILE, AND FLEXURAL STRENGTH STANDARDS.ENVIRONMENTAL CONDITIONS DURING SURFACE PREPARATION, APPLICATION, ANDCURING MUST BE MONITORED TO ENSURE PROPER EXECUTION.4.#INTERNAL AND EXTERNAL						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			COATING:O#APPLY CERAMIC-REINFORCED COMPOSITE MATERIALS FOR THE FIN AL COATINGAFTER SURFACE PREPARATION AND REBUILDING.O#THE COMPOSITE MUST WITHSTAND CONTINUOUS IMMERSION IN CHEMICALS ANDPASS THE ASTM B117 SALT FOG AND ASTM G8 CATHODIC DISBANDMENT TESTS.O#THE COATING MUST BE 800-1000 MICRONS THICK AND FINISHED WITH ASMOOTH, ABRASI ON-RESISTANT GLASS-LIKE SURFACE.O#THE COMPOSITE MATERIAL MUST BE AUTHORIZED FOR USDA INCIDENTAL FOODCONTACT APPLICATIONS AND HOLD PO TABLE WATER CERTIFICATION FROM WRAS OREQUIVALENT AUTHORITIES.O#EXTERNAL COATING SHOULD BE AN EPOXY COATING, 300-400 MICRONS THICK,IN BLUE COLOR FOR BOTH PUMPS AND VALVES.5.#WARRANTY: THE SUPPLIER MUST PROVIDE A 24-MONTH SERVICE WARRANTYAGAINST ANY DEFECTS IN THE C OATING. IF THE COATING FAILS WITHIN					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THISPERIOD, THE SUPPLIER WILL RECOAT THE EQUIPMENT FREE OF CHARGE.6.#METHOD STATEMENT: THE SUPPL IER MUST SUBMIT A DETAILED METHODSTATEMENT FOR THE COATING PROCESS, INCLUDING MATERIAL SPECIFICATIONS,FOR REVIEW AND APPROVAL.7.#INS PECTION: PRIOR TO DELIVERY, THE COATING WORK MUST BE INSPECTED BYDEWA ENGINEERS AT THE SUPPLIER'S WORKSHOP FOR FINAL ACCEPTANCE. THE CONTRACTOR MUST PROVIDE ALL NECESSARY INSPECTION TOOLS.8.#REPORTS AND DOCUMENTATION: UPON DELIVERY, THE CONTRACTOR MUST SUBMITTHE FO LLOWING:O#MATERIAL DATA SHEETS BEFORE AND AFTER COATING.O#WRAS CERTIFICATION FOR COATING MATERIALS.O#ALL RELEVANT TEST REPORTS.O#PRO PER COMPLETION REPORT INCLUDING THE INTERNAL CONDITION BEFORE ANDAFTER THE BLASTING AND THE COATING.KINDLY CONTACT MR. DHRUBA (DHRUB						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			A.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
22		ITEM-00004	COMPLETE OVERHAULING OF BOOSTER PUMP FOR NAJMA PH4 PUMPING STATION. PUMPDETAILS: AVERSA PUMP MODEL: DVL-350X300, HEAD-140M, FLOW-263 L/S,RPM-1475, 630KW.SCOPE OF WORKTHE FOLLOWING OUTLINES THE MANDATORY AND OPTIONAL SCOPE OF WORK FOR THEOVERHAUL OF BOOSTER PUMPS AN D THEIR ACCESSORIES AT THE BOOSTER PUMPINGSTATION.1.0 MANDATORY SCOPE OF WORK:A) THE CONTRACTOR IS RESPONSIBLE FOR TRANSPORTING THE PUMP ASSEMBLY TOAND FROM THE DEWA SITE TO THEIR WORKSHOP. DEWA WILL NOT PROVIDETRANSPORTATION. FOR LOADING AND UNLOADING, THE CONTRA CTOR MAY USE DEWA#SOVERHEAD CRANE AT THE PUMPING STATION, WITH PROPER COORDINATION WITHDEWA REPRESENTATIVES. B) REPLACEMENT OF THE M ECHANICAL SEAL, COUPLINGBUSH RENEWAL,	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			GLAND PACKING RENEWAL, AND BEARING REPLACEMENT ASREQUIRED. C) OVERHAULING OF THE PUMP (REFER T O ANNEXURE I FOR MANDATORYAND ANNEXURE II FOR OPTIONAL WORK). D) EXTERNAL PAINTING OF THE PUMP. E)RECTIFICATION OF ANY ISSUES THAT A RISE AFTER INSTALLATION/LOAD TESTING.THIS SHALL BE DONE ON SITE IF POSSIBLE, AND IF NOT, THE CONTRACTOR ISRESPONSIBLE IN COLLECTING THE PUMP AND MOVED IT BACK TO THEIR FACILITY.F) IF ANY PART IS FOUND DEFECTIVE, THE CONTRACTOR IS RESPONSIBLE FORREPAIRING OR REPLAC ING IT. DEWA WILL PROVIDE AVAILABLE SPARES. IF ANYSPARE PARTS ARE UNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SUBMITTHE COST F OR DEWA APPROVAL BEFORE PLACING AN ORDER. G) ONCE THE PUMP ISFULLY ASSEMBLED, THE PUMP MUST BE PRESSURE HYDRO TESTED IN THECONTRACTO					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			R FACILITY TO MAKE SURE THE PUMP IS WELL ASSEMBLED AND THATTHERE ARE NO LEAKS.2.0 REQUIREMENTS PRIOR TO QUOTATION SUBMISSION:A) THE CONTRACTOR MUST VISIT THE SITE TO FAMILIARIZE THEMSELVES WITH THESCOPE OF WORK AND POTENTIAL COMPLEXITIES BEFORE SUBMITTING A QUOTAT ION.B) DEWA WILL NOT ACCEPT ANY CLAIMS FOR ADDITIONAL CHARGES BEYOND THEAGREED RATES OR PRICES DURING OR AFTER THE EXECUTION OF THE WORK. C) THECONTRACTOR WILL BE PROVIDED WITH AN EQUIPMENT SHUTDOWN SCHEDULE INCOORDINATION WITH THE OPERATIONS & MAINTENANCE DEPARTM ENT OF THE WATERDIVISION. D) A TIME SCHEDULE OR BAR CHART SHOWING EACH ACTIVITY MUST BESUBMITTED. E) UPON COMPLETION, AN INSPECTION CHECKLIST AND QUALITYPROCEDURE DOCUMENTATION, WHERE APPLICABLE, MUST BE SUBMITTED. F) THECONTRACTOR IS RESPONSIBLE						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FOR SITE SUPERVIS ION, COORDINATION OF FIELDACTIVITIES, AND THE SUPPLY OF REQUIRED TECHNICIANS, TOOLS, EQUIPMENT,AND RESOURCES NECESSARY TO EXECUTE TH E CONTRACT.3.0 TAKEOVER:UPON COMPLETION OF ALL WORK WITHIN THE SCOPE OF THE CONTRACT, THECONTRACTOR MUST NOTIFY DEWA IN WRITING. A C ERTIFICATE OF COMPLETION WILLBE ISSUED AFTER A FINAL INSPECTION, CONFIRMING THAT THE WORK HAS BEENACCEPTED AND TAKEN OVER BY DEWA FO LLOWING THE NECESSARY CONDITIONMONITORING CHECKS.4.0 WARRANTY:A) ALL WORK WILL CARRY A WARRANTY OF 8,000 HOURS OF OPERATION OR ONEYE AR, WHICHEVER COMES FIRST. B) THE WARRANTY WILL TAKE EFFECT FROM THEDATE OF DEWA'S OFFICIAL TAKEOVER OF THE COMPLETED JOB. C) IF ANY DEFECTSARE IDENTIFIED DURING THE WARRANTY						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PERIOD, THE CONTRACTOR MUST RECTIFYTHEM WITHIN THE TIMEFRAME SET BY DEWA WITHOUT ADDITION AL COST ORCOMPENSATION.5.0 DOCUMENTATION:UPON SATISFACTORY COMPLETION OF THE WORK AND HANDOVER, THE CONTRACTORMUST SUBMIT THE FOLLOW ING DOCUMENTS TO DEWA:·#INITIAL INSPECTION REPORT (MENTIONING THE REQUIRED SPARES ANDREQUIRED ACTIONS)·#JOB COMPLETION REPORT (INCLU DING ALL OVERHAULING ACTIONS DONE) WITHINONE WEEK OF DELIVERY·#SERVICE ENTRY APPLICATION ATTACHING THE JOB COMPLETION REPORTIMMEDIAT ELY ONCE THE REPORT IS SIGNED BY DEWA REPRESENTATIVE·#INCLUDING ALL PROPER PHOTOS, EQUIPMENT SERIAL NUMBER, AND EQUIPMENTTAGGING·#RE QUISITION FOR SPARE PARTS PLANNING BASED ON THE CURRENT CONDITIONOF THE EQUIPMENTANNEXURE I # DETAILED MANDATORY SCOPE OF WORK FOR B						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OOSTER PUMP OVERHAUL1.#DISMANTLING: THE CONTRACTOR SHALL DISMANTLE THE PUMP ACCORDING TODEWA ENGINEER#S INSTRUCTIONS. SKILLED WORKMA NSHIP AND CARE MUST BEAPPLIED DURING REMOVAL.2.#OVERHAULING: THE CONTRACTOR SHALL DISMANTLE THE ROTATING ASSEMBLY INTHEIR WORKSHOP A ND RECORD ALL FINDINGS, INCLUDING PHOTOGRAPHS OFDETERIORATED COMPONENTS. THE SHAFT MUST BE INSPECTED FOR STRAIGHTNESS,AND WORN AREAS SHOULD BE RECONDITIONED. IMPELLER, BEARINGS, MECHANICALSEAL, GLAND SLEEVE, AND WEAR RINGS MUST BE THOROUGHLY CHECKED ANDREPLACED IF NECESSARY. ALL PARTS FOUND DEFECTIVE MUST BE REPAIRED ORREPLACED, WITH AVAILABLE SPARES SUPPLIED BY DEWA. IF SPARES AREUNAVAILABLE, THE CONTRACTOR MUST ARRANGE THEM AND SEEK APPROVAL FROMDEWA FOR ADDITIONAL COSTS. THE PUMP CASING MUST BE CLEANED AND					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			INSPECTEDFOR DAMAGE, AND ANY NECESSARY REPAIRS MUST BE CARRIED OUT USINGSANDBLASTING AND FOOD-GRADE EPOXY COATING.3.#ASSEMBLY: REASSEMBLY OF THE EQUIPMENT MUST FOLLOW STANDARDPROCEDURES, ENSURING THE PROPER FIT AND CLEARANCES. THE ROTOR ASSEMBLYSHOULD BE DYNAMICALLY BALANCED P ER ISO 1940/1 STANDARDS. A DETAILEDRECORD OF ALL ACTIVITIES MUST BE MAINTAINED, AND ANY DEVIATIONS FROM SETVALUES WILL BE DETERMINED BY DEWA.4.#CONSUMABLES & ACCESSORIES: MANUFACTURING OF MECHANICAL SEAL COOLINGPIPE FITTINGS, SHAFT LOCK NUTS, LOCK WASHERS, DOWEL P INS, BEARINGSPACERS, HOLDING DOWN BOLTS, AND VARIOUS GASKETS, INCLUDING THE SUPPLYOF O-RINGS SHOULD BE PROVIDED BY THE CONTRACTOR WI TH NO ADDITIONAL COST.ANNEXURE II # OPTIONAL MACHINING WORKS1.#IMPELLER MACHINING: THIS						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			INCLUDES GRIT BLASTING AND NON-DESTRUCTIVETE STING (NDT) TO IDENTIFY CRACKS, SKIMMING THE WEAR RING AREAS, ANDFITTING NEW RINGS.2.#SHAFT MACHINING: THE SHAFT WILL UNDERGO CHROME PLATING ON BEARINGSEATING AREAS AND MECHANICAL SEAL SEATING AREAS, ALONG WITH METALREBUILDING AND STRAIGHTENING (UP TO A 4-THOU MAX IMUM BEND).3.#BEARING HOUSING MACHINING: MACHINING AND RESLEEVING OF BOTH DE ANDNDE BEARING HOUSING BORES.4.#MECHANICAL SEAL FACE: M ACHINING AND REPAIRING OF THE PUMP#S TOP ANDBOTTOM CASING HALVES AT THE MECHANICAL SEAL FACE.5.#PUMP CASINGS: SKIMMING AND GROOVING OF SUCTION AND DISCHARGE FLANGESON THE PUMP CASING.MACHINING WORKS MUST COMPLY WITH THE LATEST STANDARDS, AND PRIORAPPROVAL FROM THE DEWA ENGINEER IS REQUIRED BEFORE					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			COMMENCING ANYMACHINING TASKS. ANY DAMAGES DONE ON ANY PROVIDED SPARES FROM DEWA, THECONTRACTOR IS HELD RESPONSIBLE IN REPLACING THE DAMAGED MATERIAL AT NOADDITIONAL COST TO DEWA.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV .AE) FOR FURTHERCLARIFICATION.						
23		ITEM-00004	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP CASE WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR NAJMA PH4 AVERSA PUMPSCOPE OF WORK1.#SUPPLY, M ACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP CASE WEARRING, AND INSTALL IT AS PART OF THE COMPLE TE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPL E AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ROTOR/PUMPTESTING TO VE RIFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT T ERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PR OVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTO R SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEW A.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			(DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
24		ITEM-00004	MACHINING, SUPPLY, AND ASSEMBLY OF PUMP IMPELLER WEAR RING WITH COMPLETEPUMP ASSEMBLY FOR NAJMA PH4 AVERSA PUMPSCOPE OF WORK1.#SUPPL Y, MACHINING, AND ASSEMBLYTHE CONTRACTOR SHALL SUPPLY THE MATERIAL, MACHINE THE PUMP IMPELLER WEARRING, AND INSTALL IT AS PART OF TH E COMPLETE PUMP ASSEMBLY.2.#COMPLIANCE WITH SPECIFICATIONSMATERIAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROV ED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CONTRACTOR SHALL COMPLETE THE PUMP ASSEMBLY AND PERFORM ROTOR/PUMPTESTI NG TO VERIFY PROPER OPERATION.4.#QUALITY AND ACCEPTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#P AYMENT TERMSPAYMENT SHALL BE MADE UPON	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE OFSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE C ONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL, MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL CO STTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE I NTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
25		ITEM-00004	MACHINING, SUPPLY, AND ASSEMBLY OF SHAFT SLEEVES FOR NAJMA PH4 AVERSAPUMPSCOPE OF WORK1.#SUPPLY, MACHINING, AND ASSEMBLYTHE CONTRACT OR SHALL SUPPLY THE MATERIAL, MACHINE THE	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SHAFT SLEEVES, ANDASSEMBLE THEM ONTO THE PUMP ROTOR.2.#COMPLIANCE WITH SPECIFICATIONSMATER IAL, DIMENSIONS, AND WORKMANSHIP SHALL STRICTLY COMPLY WITH THEAPPROVED SAMPLE AND DEWA SPECIFICATIONS.3.#ASSEMBLY AND TESTINGTHE CO NTRACTOR SHALL COMPLETE THE ROTOR ASSEMBLY AND PERFORM TESTING TOVERIFY PROPER FITTING, ALIGNMENT, AND OPERATION.4.#QUALITY AND ACCE PTANCEALL WORK SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE DEWAENGINEER.5.#PAYMENT TERMSPAYMENT SHALL BE MADE UPON SUCCESSFUL COMPLETION OF THE WORK ANDAPPROVAL BY THE DEWA ENGINEER.6.#WARRANTYTHE CONTRACTOR SHALL PROVIDE A ONE-YEAR WARRANTY FROM THE DATE O FSUCCESSFUL INSTALLATION, TESTING, AND ACCEPTANCE.7.#RESPONSIBILITY FOR ERRORSTHE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MATERIAL,						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			MACHINING, ORASSEMBLY DEFECTS AND SHALL REPLACE OR RECTIFY THEM AT NO ADDITIONAL COSTTO DEWA.8.#MATERIAL SUPPLYTHE CONTRACTOR SHALL PROCURE AND SUPPLY ALL REQUIRED MATERIALS, WHICHSHALL BE NEW AND SUITABLE FOR THE INTENDED SERVICE.KINDLY CONTACT MR. DHRUBA (DHRUBA .BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.					
26		ITEM-00004	MACHINING AND REBUILDING OF SHAFT FOR NAJMA PH4 AVERSA PUMPSCOPE OF WORK:1.#SHAFT REBUILDING AND MACHINING: REBUILD AND MACHINE THE PUMP SHAFTON BOTH THE DRIVE END (DE) AND NON-DRIVE END (NDE), FOCUSING ON THEMECHANICAL SEAL AND BEARING AREAS.2.#ASSEMBLY AND TESTI NG: REASSEMBLE THE PUMP AND ROTOR, FOLLOWED BYTHOROUGH TESTING TO ENSURE PROPER FUNCTIONALITY.3.#CONTRACTOR RESPONSIBILITY: THE CONT RACTOR WILL ASSUME FULLRESPONSIBILITY FOR	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ANY ERRORS OR MISHANDLING DURING THE PROCESS. ALLNECESSARY CORRECTIONS MUST BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
27		ITEM-00004	MODIFICATION OF MECHANICAL SEAL COOLING LINE FOR NAJMA PH4 AVERSA PUMPSCOPE OF WORK:1.#FABRICATION AND MODIFICATION: FABRICATE OR MO DIFY THE MECHANICALSEAL COOLING LINE TO MEET THE SPECIFIC REQUIREMENTS OF THE PUMP.2.#ASSEMBLY AND TESTING: ASSEMBLE THE COOLING LIN E TO THE PUMP ROTORASSEMBLY, ENSURING IT ADHERES TO THE ORIGINAL DESIGN SPECIFICATIONS.TEST THE COOLING LINE THOROUGHLY TO CONFIRM T HERE ARE NO ISSUES ORLEAKS.3.#CONTRACTOR RESPONSIBILITY: THE CONTRACTOR WILL BE FULLY RESPONSIBLEFOR ANY ERRORS OR MISHANDLING DURIN G THE MODIFICATION OR ASSEMBLYPROCESS. ALL	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			NECESSARY CORRECTIONS MUST BE MADE AT NO ADDITIONAL COST.KINDLY CONTACT MR. DHRUBA (DHRUB A.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						
28		ITEM-00004	FULL BLASTING AND RECOATING OF NAJMA PH4 AVERSA PUMPSPECIFICATION FOR INTERNAL COATING OF PUMPS AND VALVESTHESE PUMPS AND VALVES ARE UTILIZED IN WATER BOOSTER PUMPING STATIONS,HANDLING POTABLE WATER WITH TEMPERATURES UP TO 50°C. WHILE THE WATER ISTYPICALLY CLEAN, OCCASIONAL SAND OR SOLIDS MAY BE PRESENT IN THE STREAMFROM THE PIPELINE. THE PUMPS HAVE BEEN IN OPERATION SINCE THE STATION'SCOMMISS IONING.SCOPE OF WORK1.#COLLECTION AND TRANSPORTATION: THE CONTRACTOR IS RESPONSIBLE FORCOLLECTING THE PUMP CASING USING A SUITABLE P ICKUP OR CRANE-MOUNTEDTRUCK TO TRANSPORT IT TO DEWA'S WORKSHOP. THE	1	SET				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CONTRACTOR MUST ENSURETHE USE OF APPROPRIATE LIFTING SLINGS/BEL TS WITH SUFFICIENT LOADCAPACITY FOR SAFE LOADING AND UNLOADING.2.#SURFACE PREPARATION: BEFORE APPLYING ANY COATING, THE CONTRACTORMU ST PERFORM SURFACE PREPARATION USING SAND OR GRIT BLASTING, OR OTHERSUITABLE MECHANICAL METHODS TO REMOVE RUST AND LOOSE MATERIALS. AFTERTHE BLASTING, DEWA ENGINEERS MUST INSPECT THE SURFACE BEFORE COATING.ALL MACHINED SURFACES AND CRITICAL AREAS MUST BE ADEQUATEL Y PROTECTEDDURING SANDBLASTING TO AVOID DAMAGE. CLEAR PHOTOS MUST BE TAKEN AND BEATTACHED IN THE COMPLETION REPORT.3.#REBUILDING ERO DED/PITTED SURFACES: THE CONTRACTOR MUST RESTOREERODED SURFACES USING A SUITABLE COMPOSITE MATERIAL BEFORE APPLYING ANYCOATING. THE COMPOSITE MATERIAL MUST HAVE THE						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FOLLOWING PROPERTIES:O#SUITABLE FOR CONTINUOUS IMMERSION IN VARIOUS CHEMICALS (E.G., FERRICCHLORIDE , HYDROCHLORIC ACID, SULFURIC ACID, SODIUM HYDROXIDE, AMMONIUMHYDROXIDE) AT 21°C.O#MUST PASS THE ASTM C868 CORROSION TEST FOR DEMINE RALIZED WATERIMMERSION AT 43°C FOR AT LEAST SIX MONTHS.O#ADHESION (ASTM D1002) GREATER THAN 183 KG/CM² (2,600 PSI).O#MEET OR EXCEED COMPRESSIVE, TENSILE, AND FLEXURAL STRENGTH STANDARDS.ENVIRONMENTAL CONDITIONS DURING SURFACE PREPARATION, APPLICATION, ANDCURING MU ST BE MONITORED TO ENSURE PROPER EXECUTION.4.#INTERNAL AND EXTERNAL COATING:O#APPLY CERAMIC-REINFORCED COMPOSITE MATERIALS FOR THE F INAL COATINGAFTER SURFACE PREPARATION AND REBUILDING.O#THE COMPOSITE MUST WITHSTAND CONTINUOUS IMMERSION IN CHEMICALS ANDPASS THE AS TM B117 SALT FOG AND ASTM G8 CATHODIC					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			DISBANDMENT TESTS.O#THE COATING MUST BE 800-1000 MICRONS THICK AND FINISHED WITH ASMOOTH, ABRA SION-RESISTANT GLASS-LIKE SURFACE.O#THE COMPOSITE MATERIAL MUST BE AUTHORIZED FOR USDA INCIDENTAL FOODCONTACT APPLICATIONS AND HOLD POTABLE WATER CERTIFICATION FROM WRAS OREQUIVALENT AUTHORITIES.O#EXTERNAL COATING SHOULD BE AN EPOXY COATING, 300-400 MICRONS THICK, IN BLUE COLOR FOR BOTH PUMPS AND VALVES.5.#WARRANTY: THE SUPPLIER MUST PROVIDE A 24-MONTH SERVICE WARRANTYAGAINST ANY DEFECTS IN THE COATING. IF THE COATING FAILS WITHIN THISPERIOD, THE SUPPLIER WILL RECOAT THE EQUIPMENT FREE OF CHARGE.6.#METHOD STATEMENT: THE SUP PLIER MUST SUBMIT A DETAILED METHODSTATEMENT FOR THE COATING PROCESS, INCLUDING MATERIAL SPECIFICATIONS,FOR REVIEW AND APPROVAL.7.#I					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602795

DATE : 02.11.2026

REQ No : 1032605314

REQ TITLE : Complete pump overhauling and

DELIVERY LOCATION

CLOSING DATE : 06.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			NSPECTION: PRIOR TO DELIVERY, THE COATING WORK MUST BE INSPECTED BYDEWA ENGINEERS AT THE SUPPLIER'S WORKSHOP FOR FINAL ACCEPTANCE. T HECONTRACTOR MUST PROVIDE ALL NECESSARY INSPECTION TOOLS.8.#REPORTS AND DOCUMENTATION: UPON DELIVERY, THE CONTRACTOR MUST SUBMITTHE FOLLOWING:O#MATERIAL DATA SHEETS BEFORE AND AFTER COATING.O#WRAS CERTIFICATION FOR COATING MATERIALS.O#ALL RELEVANT TEST REPORTS.O#P ROPER COMPLETION REPORT INCLUDING THE INTERNAL CONDITION BEFORE ANDAFTER THE BLASTING AND THE COATING.KINDLY CONTACT MR. DHRUBA (DHR UBA.BANERJEE@DEWA.GOV.AE) FOR FURTHERCLARIFICATION.						

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

Complete pump overhauling and coating for several pumping stations

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602795
DATE	: 02.11.2026
REQ No	: 1032605314
REQ TITLE	: Complete pump overhauling and
DELIVERY LOCATION	
CLOSING DATE	: 06.11.2026
CLOSING TIME	: 10:00:00

STANDARD TERMS & CONDITIONS

1) RFQ Document Disclaimer: The PDF version of this Request for Quotation (RFQ) is provided for convenience only and contains a summary of key information. It does not include all technical details, requirements, or specifications. Bidders must refer to the complete system documentation and all referenced materials to obtain full and accurate information necessary for preparing their proposals.

2) Prices should be 'DDP' delivery duty paid at DEWA stores.

3) Quotation to be submitted only in local currency U.A.E Dirhams

4) DEWA Standard Payments: Payment will be made within 30 days from the date the Supplier/Contractor submits a complete and accurate invoice, together with all required supporting documents, subject to the material and/or services having been duly accepted.

5) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

6) The offered product and/or services in the Quotation, shall be confirming and in accordance with DEWA Energy Management Policy & EnMS Manual.

7) Confidentiality Clause: The Supplier/Service Provider shall treat all information and data (excluding open data) contained in the Purchase Order or obtained by the Supplier/Service Provider in connection with the execution of Works as proprietary and strictly confidential. In particular, the Supplier/ Service Provider shall not publish or disclose any data or information including but not limited to personally identifiable information, government data, project details, specifications, drawings or photographs concerning the Works to any third parties without the prior written consent of the Employer. If the Supplier/Service Provider is obligated to obtain NOCs / Permits /Permissions for the Project from Government agencies as per the terms and scope of the Contract, the Supplier/Service Provider shall submit only the specific data required for the purpose to the authorized team of the agency, through their prescribed channel / system, subject to information security requirements. The Supplier/Service Provider shall comply with all the applicable data protection laws and regulations.

8)Data Privacy, Security and Sharing:

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602795
DATE	: 02.11.2026
REQ No	: 1032605314
REQ TITLE	: Complete pump overhauling and
DELIVERY LOCATION	
CLOSING DATE	: 06.11.2026
CLOSING TIME	: 10:00:00

a) Third-party shall handle DEWA data in accordance with all applicable laws, regulations, and DEWA policies.
b) DEWA data shall not be shared outside UAE, in line with DESC ISR requirements.
c) DEWA's Non-Disclosure Agreement (NDA) and External Party Acknowledgment (EPA) shall be signed by the third-party and their sub-contractors who handle DEWA data prior to the contract commencement.
d) DEWA reserves the right to withhold data from third parties if deemed sensitive.
e) Access to data must be restricted to authorized, named third-party employees only and DEWA must be informed of any changes in employment status of those with access.
f) Third party shall not disclose, transfer or share any DEWA data with other third parties (government, semi government, private) without obtaining DEWA#s authorized data owner written approval.
g) Upon the completion/ termination of the agreement the external party shall securely delete all DEWA#s data in their custody/ control including the backup and provide written confirmation and evidence to DEWA upon the data deletion completion as per agreed data disposal process, this is to address risk of data remanence.

9) Liquidated Damages for PO total value in excess of AED 50,000:
If the Contractor/Supplier delays or fails to deliver, fails to commence or perform the services, DEWA has the right to deduct an amount equal to 1.25% per day/week of the total PO fee for the services/supplies delayed, not performed or not delivered, subject to a cap of 10% of the total PO fee without recourse to any judicial proceedings, as compensation for the delay or failure to perform. If the deducted amount exceeds 10% of the total PO fee, without prejudice to any of DEWA's rights under the applicable law, DEWA shall be entitled to terminate the PO immediately without the need for any notice or judicial proceedings against the defaulting Supplier, and without the need to prove the damage.

10) Indemnity: The Supplier shall indemnify DEWA from and against all claims, damages, costs and liabilities brought by any third party against DEWA arising out of or in connection with any of acts or omissions of the Supplier/Contractor, or any failure to perform its obligations under this PO.

11) Dispute Resolution: Any dispute arising out of or in connection with this PO shall be settled through mutual good faith negotiation and understanding between the Parties: Failing amicable settlement, the dispute shall finally be referred to the courts having appropriate jurisdiction in the Emirate of Dubai.

12) Intellectual Property Rights: The Supplier/Contractor shall not use DEWA's intellectual property, including logos, trademarks, service marks, trade names, service names, and brand names, whether in a press release or otherwise, without obtaining DEWA's prior written consent. All intellectual property rights in the deliverables created or developed, under this PO, shall be solely owned by DEWA.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602795
DATE	: 02.11.2026
REQ No	: 1032605314
REQ TITLE	: Complete pump overhauling and
DELIVERY LOCATION	
CLOSING DATE	: 06.11.2026
CLOSING TIME	: 10:00:00

13) Assignment and Transfer: The Supplier/Contractor shall not assign this PO or any part thereof without the prior written consent of DEWA. Such consent shall not relieve the Contractor of any of its obligations or duties under this PO.

14) Force Majeure: If either party is affected by a Force Majeure event, it will promptly notify the other party of the nature and extent thereof. Neither party will be deemed to be in breach of this PO, by reason of any delay or non-performance, of any of its obligations hereunder, due to any Force Majeure event of which it has notified the other party. The time for performance of these obligations will be extended accordingly as may be fair and reasonable in the circumstances. Provided always that if the duration of such delay or impediment exceeds thirty (30) days, either party may give a fifteen (15) working days' notice to terminate a specific item or the PO in its entirety.

15) Certificate of Conformity for Green Materials and Services Specifications: The Bidder shall, wherever applicable, provide a Certificate of conformity issued by accredited body/ laboratory as proof of compliance with the applicable green materials, services and specifications.

16) Taking Over Certificate: TOC shall be issued only after full delivery or completion of the service or deliverables. TOC will be issued conditionally ("conditional TOC") with the reasonable guarantee/observation in case of any defects after delivery or completion of the PO.

SUPPLIER'S REMARKS :

SUPPLIER'S SIGNATURE AND STAMP

DISCLAIMER : THIS IS A SYSTEM GENERATED DOCUMENT , DOSEN'T NEED SIGNATURE.