# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | ITEM-00001 | TECHNICAL AND GENERAL SPECIFICATION OF OUTSOURCING WORK L2 STATION,JEBEL ALI POWER STATIONTITLE: L2 STATION HRSG 83 DD HINGE INSPECT ION, REPAIR & MODIFICATIONWORK.1.#REMOVE ALL LINER PLATES AND INSULATION AND CARRY OUT INSPECTION OFDD HINGE AREA.2.#CARRY OUT ANY D EFECTS THAT ARE FOUND DURING INSPECTION3.#ARRANGE THE 10 MM PLATE MATERIAL SS 321 H (L SHAPE) FOR HINGE AREA (PLATE DEWA SCOPE)4.#AD D 10 MM PLATE MATERIAL SS 321 H (L SHAPE) FOR HINGE AREA WELDINGWITH THE CASING5.#INSULATION AND LINER PLATES TO BE REINSTALLED AFTE R INSPECTION &REPAIR.A.#DURATION:1.#07 DAYS DURING HRSG 83 2026-2027 OUTAGE ,TENTATIVE STARTING DATE10.01.2027B.#SCHEDULE1.#WORK TO BE CARRIED OUT DURING HRSG 83 OUTAGE WHICH IS TENTATIVELYSCHEDULED FOR 10.01.2027.2.#THIS SCHEDULE MAY BE CHANGE | 1 | AU | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | BASED ON OPERATIONA<br>L REQUIREMENT,ACCORDINGLY IF THERE WILL BE ANY CHANGES IT WILL BE INFORMED AND WORK TOBE CARRIED OUT ACCORDINGLY.3.#WORK WILL BE 24/<br>7 (ROUND THE HOURS 2 SHIFT ,7 DAYS PER WEEK)C.#PRE-BID SITE INSPECTION:1.#THE CONTRACTOR SHALL VISIT THE SITE AND MAKE THEMSELVES FU<br>LLYFAMILIAR WITH THE WORK SCOPE, PLANT ACCESS, FACILITIES, COMPLEXITIES,ETC., BEFORE SUBMITTING THE BID. DEWA WILL NOT ACCEPT ANY CL<br>AIM FOREXTRAS BEYOND THE ORDER RATES / PRICES DURING AND AFTER THE EXECUTION OFWORK ORDERED.2.#THE SCOPE OF WORK MENTIONED HERE ONLY<br>PROVIDES A BROAD OUTLINE OFTHE TASK. THE BIDDER MUST REVIEW THE ADEQUACY OF THE PROPOSED SCOPE OFWORK TO CARRY OUT THE REQUIRED TAS<br>KS AND ADD ANY ADDITIONAL WORK THAT ISNEEDED FOR SATISFACTORY COMPLETION OF | | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | THIS PROJECT.D.#QUALIFICATION OF BIDDER:1.#THE BIDDER SH ALL HAVE ADEQUATE AND PROVEN EXPERIENCE IN THE PAST INMAINTENANCE AND REPAIR OF DIVERTER DAMPERS. EVIDENCE TO BE PROVIDED.2.#ALL WOR K SHALL BE DONE AT SITE AS PER RECOMMENDATION AND SUPERVISIONOF DIVERTER DAMPER SPECIALIST.3.#DIVERTER DAMPER SPECIALIST MUST HAVE A T LEAST 25 YEARS OF WORKEXPERIENCE IN DD INSPECTION AND MAINTENANCE. HIS CV IS TO BE PROVIDED.E.#SCOPE OF WORK:(I)#PREPARATION1.#ALL PERSONNEL PARTICIPATING IN THE INSPECTION AND REPAIR WORK MUSTADHERE TO SITE SAFETY PROTOCOLS AND USE APPROPRIATE PERSONAL PROTECTI VEEQUIPMENT (PPE) AT ALL TIMES. ADDITIONALLY, A DETAILED WORK PLANOUTLINING THE SEQUENCE OF ACTIVITIES, REQUIRED MANPOWER, AND NECES SARYTOOLS SHOULD BE SUBMITTED PRIOR TO | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | COMMENCEMENT OF THE TASK TO ENSURESMOOTH EXECUTION.2.#MOBILIZE THE MANPOWER/EQUIPMENT WITHIN 01 DAY OF ADVANCE NOTICE.3.#OBTAIN PTW (PERMIT TO WORK) / LC (LINE CLEARANCE) & HOT WORK PERMITFROM DEWA.4.#THE FOLLOWING DOCUMENTS ARE TO BE SUBMITTED TO OBTAIN PTW,4.1.#METHOD STATEMENT4.2.#RISK ASSESSMENT OF THE WORK4.3.#TOOLBOX TALK REPORT.5.#ENSURE PROPER ISO LATION OF THE EQUIPMENT & VALID HWP IS AVAILABLE.6.#ENSURE NO FLAMMABLE MATERIALS NEAR THE HOT WORK AREA.7.#ENSURE THE AREA IS CORRE CTLY SECURED AND SAFE TO WORK ON IN ALLRESPECTS.8.#CONDUCT SITE SURVEY AND SAFETY INSPECTION TO ASSESS THE WORKINGENVIRONMENT.9.#BAR RICADE THE AREA WITH SIGNAGE.10.#VERIFY THAT SCAFFOLDS ARE SAFE TO WORK, AND VALID SCAFFOLDING TAGSARE PROVIDED PRIOR TO USE.11.#IF | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | THE WORKING ENVIRONMENT IS SAFE, THEN THE CONTRACTOR CAN PROCEEDWITH THE FOLLOWING STEPS.12.#NOTE: ALL WORKS SHALL BE AS PER RECOMME NDATION DD SPECIALIST ANDUNDER HIS SUPERVISION.(II)#REMOVAL OF LINER PLATES AND INSULATION, BLADE FRAME INSPECTION ANDMINOR REPAIR13 .#FOR HINGE AREA INSPECTION REMOVE THE LINERS AND INSULATIONS.14.#CLEANING OF THE HINGE AREA.15.#VISUAL INSPECTION OF THE ALL THE WE LDING JOINT.16.#DYE PENETRANT TESTS FOR ALL THE WELDING JOINTS.17.#REPAIR OF THE DEFECTS IF ANY18.#DYE PENETRANT TESTS FOR ALL THE W ELDING JOINTS AFTER REPAIR.19.#FABRICATE 10 MM PLATE MATERIAL SS 321 H (L SHAPE) FOR HINGE AREA (3PIECES )20.#DISMANTLE / CUTTING TH E DD CENTERING DEVICE & STOPPER SUPPORTS21.#DD STOPPER SUPPORTS CUTTING, GRINDING BY THE HELP OF | | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | GRINDINGMACHINE.22.#DD STOPPER BALL GROOVED TO MAKE CORRECT SHAPE.23.#WELDING THE 10 MM PLATE MATERIAL SS 321 H (L SHAPE) (3 PIECES)WITH THE CS CASING AND LINERS24.#TH EN REFIXING DD CENTERING DEVICE & STOPPER SUPPORT BROUGHT OUT TOTHE CORRECT DIMENSIONAND REQUIRED TEMPORARY SUPPORTS PROVIDE TO HOLD THE CORRECT POSITION (3MM GAP TO BE MAINTAINED BOTH SIDES).25.#AFTER THE WELDING PROCESS ALL, TEMPORARY SUPPORTS REMOVED ANDBUFFED PROPERLY.26.#FIXING AND RETHREADING THE INSULATION PINS.27.#INSTALLATION OF THE INSTALLATION AND LINER PLATE(III)#GENERAL1.#REMOVE T EMPORARY SUPPORT IF ANY.2.#REMOVE ALL METAL SCRAPS, TEMPORARY SUPPORTS AND ANY OTHER SCRAPSFROM THE WORKPLACE AND DISPOSE AS PER DEW A ENGINEER#S INSTRUCTION.3.#AFTER COMPLETION OF THE SCOPE OF WORK, A JOINT | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | INSPECTION SHALL BEDONE WITH DEWA ENGINEER.4.#CARRY OUT D AMPER HRSG CLOSE, BYPASS CLOSE AND EMERGENCY CLOSE TEST5.#A QUALIFIED JOB SUPERVISOR SHALL BE ASSIGNED FOR THE JOB.6.#SKILLED FABRIC ATORS / QUALIFIED WELDERS SHALL CARRY OUT ALL THEJOBS.7.#WELD JOINTS TO BE MADE BY QUALIFIED WELDER ACCORDING TO APPLICABLEWPS & ASM E REQUIREMENTS. (PQR, WPS & WELDER CERTIFICATES TO BE PROVIDEDIN ADVANCE)8.#CERTIFIED AND QUALIFIED RIGGERS TO BE ENGAGED FOR ALL RI GGING WORK.9.#HOUSEKEEPING AND DISPOSAL OF WASTE TO BE DONE BEFORE SITE CLEARANCE.10.#DE-MOBILIZE MEN AND EQUIPMENT AFTER COMPLETION OF THE JOB.11.#WORK COMPLETION REPORT TO BE SUBMITTED. THE REPORT SHALL CONTAINRELEVANT PHOTOS AND QUALITY DOCUMENTS.12.#ALL CONSUM ABLES, TOOLS & TACKLES ARE IN CONTRACTOR'S | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | SCOPE.13.#PROPER AND TESTED TOOLS TO BE USED.14.#ALL LIFTING & POWER TOOLS SHALL HAVE A V<br>ALID 3RD PARTY TESTCERTIFICATE AND TO BE SUBMITTED TO DEWA IN ADVANCE.15.#WELDING MACHINES SHALL HAVE A VALID 3RD PARTY CALIBRATIONC<br>ERTIFICATE AND TO BE SUBMITTED TO DEWA IN ADVANCE.16.#WORK COMPLETION REPORT, FULL REPAIRING REPORTS, MATERIAL TESTCERTIFICATES, WEL<br>DING CONSUMABLE & MATERIAL TEST CERTIFICATES TO BESUBMITTED TO DEWA17.#DEWA SCOPE:17.1.#SCAFFOLDING (CONTRACTOR TO PROVIDE REQUIREME<br>NT IN ADVANCE)17.2.#SUPPLY OF PLATE FOR SHIMS FABRICATION, INSULATION STUDS,INSULATION IF<br>REQUIRED.17.3.#NDEF.#WARRANTY1.#THE WARRAN<br>TY PERIOD FOR THE WORK SHALL BE 01 YEAR FROM THE DATE OFCOMPLETION OF WORK CERTIFIED BY DEWA.2.#IN CASE OF ANY | | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | DAMAGE/DEFECT OF THE WORK CARRIED OUT UNDER THISCONTRACT WITHIN THIS WARRANTY PERIOD, THE CONTRACTOR SHALL ATTEND ANDCARRY OUT THE NECESSARY REPAIR WORK AND RECTIFY THE DEFECT WITHIN SHORTPERIOD.G.#GENERAL TERMS & CONDITIONS1.#THE CONTRACTOR SHALL HAVE PREVIOUS WORK EXPERIENCE FOR THE SAME JOB2.#THE CONTRACTOR SHALL SUBMIT THE METHOD OF STATEMENT AND SCHEDULEUPON RECEIPT OF PO.3.#ALL TRANSPORTING AND REQUIRED EQUI PMENT SHOULD BE ARRANGED BY THECONTRACTOR. THESE EQUIPMENT SHOULD BE DULY TESTED AND CERTIFIED BY THE3RD PARTY INSPECTION AGENCY AND THE CERTIFICATES SHOULD BE PRODUCED ONDEMAND. QUALIFIED MECHANICS SHOULD BE PROVIDED.4.#THE CONTRACTOR SHALL VISIT THE SITE AND MAK E HIMSELF FULLY FAMILIARWITH THE WORK SCOPE, PLANT ACCESS, FACILITIES, | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | COMPLEXITIES, SAFETYMEASURES ETC., BEFORE HE SUBMITS HIS BID.<br>5.#THE CONTRACTOR SHALL ENSURE HOUSEKEEPING ON A DAILY BASIS AND THECONTRACTOR SHALL BE RESPONSIBLE FOR ALL WASTE MATERIAL DISPOSALS TODESIGNATED PLACES.6.#ALL DEWA SAFETY & ENVIRONMENT POLICY, RULES AND REGULATIONS SHALL BEFOLLOWED AT WORK SITE DURING THE EXECUTI<br>ON OF THE WORK. THE CONTRACTOR#SENGINEER SHOULD BE FAMILIAR WITH SAFETY REGULATIONS WHILE WORKING IN AHAZARDOUS AREA.7.#SCAFFOLDING<br>IF REQUIRED SHALL BE ARRANGED BY DEWA.8.#THE WORK SHALL BE EXECUTED UNDER DEWA SUPERVISION AND AS PERQUALITY/SCHEDULE REQUIREMENT.9. #CONTRACTOR#S SUPERVISOR SHALL BE AVAILABLE AT SITE THROUGHOUT THEPERIOD OF WORK.10.#DEWA WILL ARRANGE NECESSARY PTW / LC / HWP FROM OPERATION, CHEMICALLAB / FIRE DEPARTMENT | | | | | |

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

**RFQ NUMBER** : 2332602819

**DATE** : 05.11.2026

**REQ No** : 1032604405

**REQ TITLE** : HRSG83 DD HINGE

**DELIVERY LOCATION**

**CLOSING DATE** : 11.11.2026

**CLOSING TIME** : 10:00:00

| SL NO | ITEM CODE | SERVICE ID | DESCRIPTION | QTY | UOM | BRAND/ORIGIN | WARRANTY | UNIT PRICE | TOTAL PRICE |
|---|---|---|---|---|---|---|---|---|---|
| | | | CLEARANCES TO CARRY OUT THE SCOPE OF WORK UNDERTHIS CONTRACT.11.#THE CONTRACTOR UPON RECEI VING THE WORK PERMIT SHALL FIRST ENSURE ASAFE WORKING CONDITION.12.#ALL THE STAFF SHOULD WEAR ALL THE REQUIRED PPE WHILE AT WORK.13. #ALL MATERIAL AND TOOLS BROUGHT IN SHALL BE DECLARED AT THE POWERSTATION SECURITY GATE AND THE LIST OF THESE ITEMS S | | | | | |

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

**SPECIAL NOTES / INSTRUCTIONS:**

HRSG83 DD HINGE INSPECTION,REPAIR AND MODIFICATION WORK-L2 STATION

CONTACT DETAILS:

PRIYABRATA BEHERA

MAIL ID-priyabrata.behera@dewa.gov.ae

M-+971524230464

**STANDARD TERMS & CONDITIONS**

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

| | |
|---|---|
| **RFQ NUMBER** | : 2332602819 |
| **DATE** | : 05.11.2026 |
| **REQ No** | : 1032604405 |
| **REQ TITLE** | : HRSG83 DD HINGE |
| **DELIVERY LOCATION** | |
| **CLOSING DATE** | : 11.11.2026 |
| **CLOSING TIME** | : 10:00:00 |

1) RFQ Document Disclaimer: The PDF version of this Request for Quotation (RFQ) is provided for convenience only and contains a summary of key information. It does not include all technical details, requirements, or specifications. Bidders must refer to the complete system documentation and all referenced materials to obtain full and accurate information necessary for preparing their proposals.

2) Prices should be 'DDP' delivery duty paid at DEWA stores.

3) Quotation to be submitted only in local currency U.A.E Dirhams

4) DEWA Standard Payments: Payment will be made within 30 days from the date the Supplier/Contractor submits a complete and accurate invoice, together with all required supporting documents, subject to the material and/or services having been duly accepted.

5) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

6) The offered product and/or services in the Quotation, shall be confirming and in accordance with DEWA Energy Management Policy & EnMS Manual.

7) Confidentiality Clause: The Supplier/Service Provider shall treat all information and data (excluding open data) contained in the Purchase Order or obtained by the Supplier/Service Provider in connection with the execution of Works as proprietary and strictly confidential. In particular, the Supplier/ Service Provider shall not publish or disclose any data or information including but not limited to personally identifiable information, government data, project details, specifications, drawings or photographs concerning the Works to any third parties without the prior written consent of the Employer. If the Supplier/Service Provider is obligated to obtain NOCs / Permits /Permissions for the Project from Government agencies as per the terms and scope of the Contract, the Supplier/Service Provider shall submit only the specific data required for the purpose to the authorized team of the agency, through their prescribed channel / system, subject to information security requirements. The Supplier/Service Provider shall comply with all the applicable data protection laws and regulations.

8)Data Privacy, Security and Sharing:
a) Third-party shall handle DEWA data in accordance with all applicable laws, regulations, and DEWA policies.
b) DEWA data shall not be shared outside UAE, in line with DESC ISR requirements.

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

| | |
|---|---|
| **RFQ NUMBER** | : 2332602819 |
| **DATE** | : 05.11.2026 |
| **REQ No** | : 1032604405 |
| **REQ TITLE** | : HRSG83 DD HINGE |
| **DELIVERY LOCATION** | |
| **CLOSING DATE** | : 11.11.2026 |
| **CLOSING TIME** | : 10:00:00 |

c) DEWA's Non-Disclosure Agreement (NDA) and External Party Acknowledgment (EPA) shall be signed by the third-party and their sub-contractors who handle DEWA data prior to the contract commencement.
d) DEWA reserves the right to withhold data from third parties if deemed sensitive.
e) Access to data must be restricted to authorized, named third-party employees only and DEWA must be informed of any changes in employment status of those with access.
f) Third party shall not disclose, transfer or share any DEWA data with other third parties (government, semi government, private) without obtaining DEWA#s authorized data owner written approval.
g) Upon the completion/ termination of the agreement the external party shall securely delete all DEWA#s data in their custody/ control including the backup and provide written confirmation and evidence to DEWA upon the data deletion completion as per agreed data disposal process, this is to address risk of data remanence.

9) Liquidated Damages for PO total value in excess of AED 50,000:
If the Contractor/Supplier delays or fails to deliver, fails to commence or perform the services, DEWA has the right to deduct an amount equal to 1.25% per day/week of the total PO fee for the services/supplies delayed, not performed or not delivered, subject to a cap of 10% of the total PO fee without recourse to any judicial proceedings, as compensation for the delay or failure to perform. If the deducted amount exceeds 10% of the total PO fee, without prejudice to any of DEWA's rights under the applicable law, DEWA shall be entitled to terminate the PO immediately without the need for any notice or judicial proceedings against the defaulting Supplier, and without the need to prove the damage.

10) Indemnity: The Supplier shall indemnify DEWA from and against all claims, damages, costs and liabilities brought by any third party against DEWA arising out of or in connection with any of acts or omissions of the Supplier/Contractor, or any failure to perform its obligations under this PO.

11) Dispute Resolution: Any dispute arising out of or in connection with this PO shall be settled through mutual good faith negotiation and understanding between the Parties: Failing amicable settlement, the dispute shall finally be referred to the courts having appropriate jurisdiction in the Emirate of Dubai.

12) Intellectual Property Rights: The Supplier/Contractor shall not use DEWA's intellectual property, including logos, trademarks, service marks, trade names, service names, and brand names, whether in a press release or otherwise, without obtaining DEWA's prior written consent. All intellectual property rights in the deliverables created or developed, under this PO, shall be solely owned by DEWA.

13) Assignment and Transfer: The Supplier/Contractor shall not assign this PO or any part thereof without the prior written consent of DEWA. Such consent shall not relieve the Contractor of any of its obligations or duties under this PO.

# REQUEST FOR QUOTATION
# LOCAL PURCHASE SECTION

| | |
|---|---|
| **RFQ NUMBER** | : 2332602819 |
| **DATE** | : 05.11.2026 |
| **REQ No** | : 1032604405 |
| **REQ TITLE** | : HRSG83 DD HINGE |
| **DELIVERY LOCATION** | |
| **CLOSING DATE** | : 11.11.2026 |
| **CLOSING TIME** | : 10:00:00 |

14) Force Majeure: If either party is affected by a Force Majeure event, it will promptly notify the other party of the nature and extent thereof. Neither party will be deemed to be in breach of this PO, by reason of any delay or non-performance, of any of its obligations hereunder, due to any Force Majeure event of which it has notified the other party. The time for performance of these obligations will be extended accordingly as may be fair and reasonable in the circumstances. Provided always that if the duration of such delay or impediment exceeds thirty (30) days, either party may give a fifteen (15) working days' notice to terminate a specific item or the PO in its entirety.

15) Certificate of Conformity for Green Materials and Services Specifications: The Bidder shall, wherever applicable, provide a Certificate of conformity issued by accredited body/ laboratory as proof of compliance with the applicable green materials, services and specifications.

16) Taking Over Certificate: TOC shall be issued only after full delivery or completion of the service or deliverables. TOC will be issued conditionally ("conditional TOC") with the reasonable guarantee/observation in case of any defects after delivery or completion of the PO.

**SUPPLIER'S REMARKS :**

**SUPPLIER'S SIGNATURE AND STAMP**



DISCLAIMER : THIS IS A SYSTEM GENERATED DOCUMENT , DOSEN'T NEED SIGNATURE.