REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	E STATION, GT-E2 & GT-E3 REPLACEMENT OF THE FOUR EXISTING ON SERVICEACCUMULATORS ALONG WITH PIPING MODIFICATION1. OBJECTIVETHIS WORK COVERS THE REPLACEMENT OF THE EXISTING SERVICE ACCUMULATORS ATGT#E2 AND GT#E3, INCLUDING THE REMOVAL OF FOUR (4) EXISTING ACCUMULAT ORSAND INSTALLATION OF FOUR (4) NEW ACCUMULATORS (TWO ACCUMULATORS PERUNIT), TOGETHER WITH ALL REQUIRED PIPING MODIFICATIONS AND STR UCTURALSUPPORT ADJUSTMENTS TO ALIGN AND CONNECT THE NEW ACCUMULATOR CONNECTIONSWITH THE EXISTING WATER SUPPLY LINE.2. SCOPE OF WORKT HE CONTRACTOR SHALL PROVIDE ALL REQUIRED MANPOWER, SUPERVISION, TOOLS,LIFTING EQUIPMENT, CONSUMABLES, FITTINGS, AND MATERIALS NECESS ARY TOCOMPLETE THE WORKS.THE FOLLOWING ACTIVITIES SHALL BE CARRIED OUT FOR EACH UNIT (GT#E2 ANDGT#E3):- ISOLATE AND	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			DISCONNECT THE E XISTING PIPING FROM THE TWO INSTALLEDACCUMULATORS.- REMOVE THE EXISTING ACCUMULATORS, INCLUDING ALL ASSOCIATED SUPPORTS,ANCHOR BOLTS , AND BASE ARRANGEMENTS.- SINCE THE NEW ACCUMULATORS HAVE A LOWER HEIGHT FROM THE BASE COMPAREDTO THE EXISTING ONES, ADJUSTMENT REQU IRED FOR THE HEIGHT OF THE NEWACCUMULATORS BY DESIGN, FABRICATING, AND INSTALL ADDITIONAL BASE/LEGEXTENSIONS (ONE SET PER ACCUMULATO R LEG) TO ACHIEVE THE REQUIRED HEIGHT.- PROVIDE AND INSTALL SUITABLE BASE PLATES, SHIMS, ANCHOR BOLTARRANGEMENTS, AND ANTI#CORROSION COATING/PROTECTION AS PER SITESTANDARD.- INSTALL AND SECURE THE TWO NEW ACCUMULATORS AT THE DESIGNATEDINSTALLATION LOCATION.- MODIF Y THE EXISTING PIPING AND ALIGN THE NEW ACCUMULATOR CONNECTIONSWITH THE CURRENT						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			WATER SUPPLY PIPING.- SUPPLY AND INSTALL SS316L FITT INGS AND ACCESSORIES AS PER SITEREQUIREMENTS INCLUDING BUT NOT LIMITED TO: CONCENTRIC REDUCERS, UNIONS,SLIP-ON FLANGES, HEX NIPPLES, THREADED ELBOWS, ¾ DRAIN VALVES AND ANYADDITIONAL FITTINGS REQUIRED FOR A COMPLETE INSTALLATION.- CARRY OUT ALL WELDING, FABRICATIO N, AND PIPING WORKS REQUIRED TOCOMPLETE THE INSTALLATION.- DYE PENETRANT TESTING (PT) SHALL BE CARRIED OUT ON ALL WELDED JOINTS.- EN SURE PROPER FIT-UP, ALIGNMENT, SECURE CONNECTIONS, AND LEAK#FREEINSTALLATION.- ENSURE PROPER HOUSEKEEPING AND REMOVE ALL DEBRIS, SCR AP, AND LEFTOVERMATERIALS FROM THE WORK AREA.3. TESTING AND COMPLETIONAFTER INSTALLATION, THE CONTRACTOR SHALL CHECK ALL CONNECTIONS , ENSUREPROPER ALIGNMENT, AND PERFORM						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			LEAK TESTING. ANY DEFECTS SHALL BERECTIFIED BEFORE HANDING OVER THE SYSTEM FOR OPERATION.4. SA FETYALL ACTIVITIES SHALL BE PERFORMED IN ACCORDANCE WITH PLANT SAFETYPROCEDURES, INCLUDING OBTAINING THE REQUIRED WORK PERMITS, USE OF PROPERPPE, SAFE HANDLING OF EQUIPMENT AND MATERIALS, AND SUBMISSION OF A WORKRISK ASSESSMENT AND METHOD STATEMENT FOR APPROVAL PR IOR TO ISSUANCE OFTHE WORK PERMIT.5. WORK EXECUTION PERIODTHE SCOPE OF WORK IS PLANNED TO BE EXECUTED DURING THE NEXT OUTAGESEASON S CHEDULED BETWEEN JANUARY 2027 AND APRIL 2027. THE CONTRACTORSHALL BE NOTIFIED OF THE EXACT OUTAGE DATES AND WORK EXECUTION SCHEDULEF OR EACH UNIT PRIOR TO THE ISSUANCE OF THE PURCHASE ORDER.						
2		ITEM-00001	E STATION, GT-E2 & GT-E3 REPLACEMENT OF THE FOUR EXISTING ON SERVICEACCUMULATORS	2	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			ALONG WITH PIPING MODIFICATION1. OBJECTIVETHIS WORK COVERS THE REPLACEMENT OF THE EXISTING SERVICE ACCUMULATORS ATGT#E2 AND GT#E3, INCLUDING THE REMOVAL OF FOUR (4) EXISTING ACCUMULAT ORSAND INSTALLATION OF FOUR (4) NEW ACCUMULATORS (TWO ACCUMULATORS PERUNIT), TOGETHER WITH ALL REQUIRED PIPING MODIFICATIONS AND STR UCTURALSUPPORT ADJUSTMENTS TO ALIGN AND CONNECT THE NEW ACCUMULATOR CONNECTIONSWITH THE EXISTING WATER SUPPLY LINE.2. SCOPE OF WORKT HE CONTRACTOR SHALL PROVIDE ALL REQUIRED MANPOWER, SUPERVISION, TOOLS,LIFTING EQUIPMENT, CONSUMABLES, FITTINGS, AND MATERIALS NECESS ARY TOCOMPLETE THE WORKS.THE FOLLOWING ACTIVITIES SHALL BE CARRIED OUT FOR EACH UNIT (GT#E2 ANDGT#E3):- ISOLATE AND DISCONNECT THE E XISTING PIPING FROM THE TWO					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			INSTALLEDACCUMULATORS.- REMOVE THE EXISTING ACCUMULATORS, INCLUDING ALL ASSOCIATED SUPPORTS,ANCHOR BOLTS , AND BASE ARRANGEMENTS.- SINCE THE NEW ACCUMULATORS HAVE A LOWER HEIGHT FROM THE BASE COMPAREDTO THE EXISTING ONES, ADJUSTMENT REQU IRED FOR THE HEIGHT OF THE NEWACCUMULATORS BY DESIGN, FABRICATING, AND INSTALL ADDITIONAL BASE/LEGEXTENSIONS (ONE SET PER ACCUMULATO R LEG) TO ACHIEVE THE REQUIRED HEIGHT.- PROVIDE AND INSTALL SUITABLE BASE PLATES, SHIMS, ANCHOR BOLTARRANGEMENTS, AND ANTI#CORROSION COATING/PROTECTION AS PER SITESTANDARD.- INSTALL AND SECURE THE TWO NEW ACCUMULATORS AT THE DESIGNATEDINSTALLATION LOCATION.- MODIF Y THE EXISTING PIPING AND ALIGN THE NEW ACCUMULATOR CONNECTIONSWITH THE CURRENT WATER SUPPLY PIPING.- SUPPLY AND INSTALL SS316L FITT						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			INGS AND ACCESSORIES AS PER SITEREQUIREMENTS INCLUDING BUT NOT LIMITED TO: CONCENTRIC REDUCERS, UNIONS,SLIP-ON FLANGES, HEX NIPPLES, THREADED ELBOWS, ¾ DRAIN VALVES AND ANYADDITIONAL FITTINGS REQUIRED FOR A COMPLETE INSTALLATION.- CARRY OUT ALL WELDING, FABRICATIO N, AND PIPING WORKS REQUIRED TOCOMPLETE THE INSTALLATION.- DYE PENETRANT TESTING (PT) SHALL BE CARRIED OUT ON ALL WELDED JOINTS.- EN SURE PROPER FIT-UP, ALIGNMENT, SECURE CONNECTIONS, AND LEAK#FREEINSTALLATION.- ENSURE PROPER HOUSEKEEPING AND REMOVE ALL DEBRIS, SCR AP, AND LEFTOVERMATERIALS FROM THE WORK AREA.3. TESTING AND COMPLETIONAFTER INSTALLATION, THE CONTRACTOR SHALL CHECK ALL CONNECTIONS , ENSUREPROPER ALIGNMENT, AND PERFORM LEAK TESTING. ANY DEFECTS SHALL BERECTIFIED BEFORE HANDING OVER THE SYSTEM FOR					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602917

DATE : 13.11.2026

REQ No : 1032605318

REQ TITLE : E STATION - PHASE 1; GE

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OPERATION.4. SA FETYALL ACTIVITIES SHALL BE PERFORMED IN ACCORDANCE WITH PLANT SAFETYPROCEDURES, INCLUDING OBTAINING THE REQUIRED WORK PERMITS, USE OF PROPERPPE, SAFE HANDLING OF EQUIPMENT AND MATERIALS, AND SUBMISSION OF A WORKRISK ASSESSMENT AND METHOD STATEMENT FOR APPROVAL PR IOR TO ISSUANCE OFTHE WORK PERMIT.5. WORK EXECUTION PERIODTHE SCOPE OF WORK IS PLANNED TO BE EXECUTED DURING THE NEXT OUTAGESEASON S CHEDULED BETWEEN JANUARY 2027 AND APRIL 2027. THE CONTRACTORSHALL BE NOTIFIED OF THE EXACT OUTAGE DATES AND WORK EXECUTION SCHEDULEF OR EACH UNIT PRIOR TO THE ISSUANCE OF THE PURCHASE ORDER.						

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

E STATION - PHASE 1; GE FRAME 9E GAS TURBINE UNITS; REMOVAL OF EXISTING

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602917
DATE	: 13.11.2026
REQ No	: 1032605318
REQ TITLE	: E STATION - PHASE 1; GE
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

OFF-BASE COOLING WATER ACCUMULATORS AND INSTALLATION OF NEW ACCUMULATORS
FOR GT-E2 <(>&<)> GT-E3; QUANTITY: 2 NOS. OF ACCUMULATORS PER UNIT,
TOTAL 4 NOS.

FOR FURTHER DETAILS, PLEASE CONTACT: AHMED ZAKARIA (0524781810)
AHMED.ELDALY@DEWA.GOV.AE / MARWAN AL MHEIRI (0501136322) MARWAN.ALMH
EIRI@DEWA.GOV.AE

STANDARD TERMS & CONDITIONS

1) RFQ Document Disclaimer: The PDF version of this Request for Quotation (RFQ) is provided for convenience only and contains a summary of key information. It does not include all technical details, requirements, or specifications. Bidders must refer to the complete system documentation and all referenced materials to obtain full and accurate information necessary for preparing their proposals.

2) Prices should be 'DDP' delivery duty paid at DEWA stores.

3) Quotation to be submitted only in local currency U.A.E Dirhams

4) DEWA Standard Payments: Payment will be made within 30 days from the date the Supplier/Contractor submits a complete and accurate invoice, together with all required supporting documents, subject to the material and/or services having been duly accepted.

5) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602917
DATE	: 13.11.2026
REQ No	: 1032605318
REQ TITLE	: E STATION - PHASE 1; GE
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

6) The offered product and/or services in the Quotation, shall be confirming and in accordance with DEWA Energy Management Policy & EnMS Manual.

7) Confidentiality Clause: The Supplier/Service Provider shall treat all information and data (excluding open data) contained in the Purchase Order or obtained by the Supplier/Service Provider in connection with the execution of Works as proprietary and strictly confidential. In particular, the Supplier/ Service Provider shall not publish or disclose any data or information including but not limited to personally identifiable information, government data, project details, specifications, drawings or photographs concerning the Works to any third parties without the prior written consent of the Employer. If the Supplier/Service Provider is obligated to obtain NOCs / Permits /Permissions for the Project from Government agencies as per the terms and scope of the Contract, the Supplier/Service Provider shall submit only the specific data required for the purpose to the authorized team of the agency, through their prescribed channel / system, subject to information security requirements. The Supplier/Service Provider shall comply with all the applicable data protection laws and regulations.

8)Data Privacy, Security and Sharing:
a) Third-party shall handle DEWA data in accordance with all applicable laws, regulations, and DEWA policies.
b) DEWA data shall not be shared outside UAE, in line with DESC ISR requirements.
c) DEWA's Non-Disclosure Agreement (NDA) and External Party Acknowledgment (EPA) shall be signed by the third-party and their sub-contractors who handle DEWA data prior to the contract commencement.
d) DEWA reserves the right to withhold data from third parties if deemed sensitive.
e) Access to data must be restricted to authorized, named third-party employees only and DEWA must be informed of any changes in employment status of those with access.
f) Third party shall not disclose, transfer or share any DEWA data with other third parties (government, semi government, private) without obtaining DEWA#s authorized data owner written approval.
g) Upon the completion/ termination of the agreement the external party shall securely delete all DEWA#s data in their custody/ control including the backup and provide written confirmation and evidence to DEWA upon the data deletion completion as per agreed data disposal process, this is to address risk of data remanence.

9) Liquidated Damages for PO total value in excess of AED 50,000:
If the Contractor/Supplier delays or fails to deliver, fails to commence or perform the services, DEWA has the right to deduct an amount equal to 1.25% per day/week of the total PO fee for the services/supplies delayed, not performed or not delivered, subject to a cap of 10% of the total PO fee without recourse to any judicial proceedings, as compensation for the delay or failure to perform. If the deducted amount exceeds 10% of the total PO fee, without prejudice to any of DEWA's rights under the applicable law, DEWA shall be entitled to terminate the PO immediately without the need for

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602917
DATE	: 13.11.2026
REQ No	: 1032605318
REQ TITLE	: E STATION - PHASE 1; GE
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

any notice or judicial proceedings against the defaulting Supplier, and without the need to prove the damage.

10) Indemnity: The Supplier shall indemnify DEWA from and against all claims, damages, costs and liabilities brought by any third party against DEWA arising out of or in connection with any of acts or omissions of the Supplier/Contractor, or any failure to perform its obligations under this PO.

11) Dispute Resolution: Any dispute arising out of or in connection with this PO shall be settled through mutual good faith negotiation and understanding between the Parties: Failing amicable settlement, the dispute shall finally be referred to the courts having appropriate jurisdiction in the Emirate of Dubai.

12) Intellectual Property Rights: The Supplier/Contractor shall not use DEWA's intellectual property, including logos, trademarks, service marks, trade names, service names, and brand names, whether in a press release or otherwise, without obtaining DEWA's prior written consent. All intellectual property rights in the deliverables created or developed, under this PO, shall be solely owned by DEWA.

13) Assignment and Transfer: The Supplier/Contractor shall not assign this PO or any part thereof without the prior written consent of DEWA. Such consent shall not relieve the Contractor of any of its obligations or duties under this PO.

14) Force Majeure: If either party is affected by a Force Majeure event, it will promptly notify the other party of the nature and extent thereof. Neither party will be deemed to be in breach of this PO, by reason of any delay or non-performance, of any of its obligations hereunder, due to any Force Majeure event of which it has notified the other party. The time for performance of these obligations will be extended accordingly as may be fair and reasonable in the circumstances. Provided always that if the duration of such delay or impediment exceeds thirty (30) days, either party may give a fifteen (15) working days' notice to terminate a specific item or the PO in its entirety.

15) Certificate of Conformity for Green Materials and Services Specifications: The Bidder shall, wherever applicable, provide a Certificate of conformity issued by accredited body/ laboratory as proof of compliance with the applicable green materials, services and specifications.

16) Taking Over Certificate: TOC shall be issued only after full delivery or completion of the service or deliverables. TOC will be issued conditionally ("conditional TOC") with the reasonable guarantee/observation in case of any defects after delivery or completion of the PO.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602917
DATE	: 13.11.2026
REQ No	: 1032605318
REQ TITLE	: E STATION - PHASE 1; GE
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

SUPPLIER'S REMARKS :

SUPPLIER'S SIGNATURE AND STAMP

DISCLAIMER : THIS IS A SYSTEM GENERATED DOCUMENT , DOSEN'T NEED SIGNATURE.