REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	1.1) ROOF AREA: REMOVE EXISTING RAINWATER TRAP AND GRAVEL WITHINAPPROXIMATELY 1.0 M × 1.0 M AREA, CARRY OUT WATERPROOFING INCLUDINGS URFACE PREPARATION, JOINT AND CORNER TREATMENT, FINISHING AND WATERTESTING, AND REINSTATE THE RAINWATER TRAP AND GRAVEL, COMPLETE AS PERAPPROVED SPECIFICATIONS AND PROJECT REQUIREMENTS.	1	NO				
2		ITEM-00001	1.2) ROOF AREA: SEAL EXISTING CABLE ENTRY GAP AT MEP SHAFT,APPROXIMATELY 0.50 M × 0.15 M, INCLUDING SURFACE PREPARATION, SUITABLEBAC KING ROD/FILLER, SEALANT AND WATERPROOFING TREATMENT, COMPLETE TOPREVENT RAINWATER INGRESS AS PER APPROVED SPECIFICATIONS AND PROJEC TREQUIREMENTS.	1	NO				
3		ITEM-00001	1.3) ROOF AREA: SUPPLY AND APPLY APPROVED WATERPROOFING AND SEALINGSYSTEM AROUND EXISTING FIREFIGHTING PIPE PENETRATION, APPROXIMATE	1	NO				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			LY 0.80M × 0.80 M, INCLUDING SURFACE PREPARATION, JOINT AND CORNER TREATMENT,SEALING, FINISHING AND WATER TESTING, COMPLETE TO PREVE NT RAINWATERLEAKAGE AS PER APPROVED SPECIFICATIONS AND PROJECT REQUIREMENTS.						
4		ITEM-00001	1.4) 3D LAB: SUPPLY AND APPLY APPROVED EXTERIOR-GRADE WATERPROOF SEALINGSYSTEM TO ROOF GLASS JOINTS, INCLUDING JOINT PREPARATION, SU ITABLE JOINTFILLER/BACKING MATERIAL, WATER- AND ALKALI-RESISTANT SEALANT, TREATMENTOF JOINTS, CORNERS AND PENETRATIONS, AND ALL NECE SSARY ACCESSORIES,COMPLETE AS PER APPROVED SPECIFICATIONS AND PROJECT REQUIREMENTS.	17	M				
5		ITEM-00001	1.5) 3D LAB: SUPPLY AND INSTALL ALUMINIUM SHEET SIDE AND CORNER FLASHINGAROUND EXISTING GLASS ROOF OPENING, INCLUDING NECESSARY CUTT ING,FORMING, OVERLAPS, FIXINGS, CORNER TREATMENT, WATERPROOF SEALANT,FINISHING	15	M				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AND WATER TESTING, COMPLETE AS PER APPROVED SPECIFICA TIONS ANDPROJECT REQUIREMENTS.						
6		ITEM-00001	1.6) 3D LAB ENTRANCE: SUPPLY AND INSTALL ALUMINIUM WEATHER CANOPY/COVERABOVE THE LABORATORY ENTRANCE DOOR TO PREVENT RAINWATER INGRE SS, USINGMINIMUM 0.7 MM THICK EXTERNAL-GRADE ALUMINIUM SHEET, COMPLETE WITHSUITABLE SUPPORTING FRAME, BRACKETS, CORROSION-RESISTANT FIXINGS,FLASHINGS, SEALANT AND ALL NECESSARY ACCESSORIES. PROVIDE APPROVEDPROTECTIVE COATING/FINISH SUITABLE FOR UAE EXTERNAL WEATHE R CONDITIONSAND ADEQUATE OUTWARD SLOPE FOR PROPER RAINWATER RUNOFF. ALL CONNECTIONSTO THE EXISTING STRUCTURE SHALL BE SECURELY FIXED AND PROPERLYSEALED/WATERPROOFED. COMPLETE IN ALL RESPECTS AS PER APPROVED DETAILSAND SITE REQUIREMENTS.SIZE: 1.5M X 2.25M	3	M2				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
7		ITEM-00001	1.7) 3D LAB ENTRANCE: REMOVE APPROXIMATELY 30 MM DEPTH OF THE EXISTINGFLOOR FINISH/SUBSTRATE AT THE LABORATORY ENTRANCE BY CONTROLLE D CHIPPINGAND GRINDING, AND REINSTATE THE FLOOR USING APPROVED REPAIR MATERIAL TOFORM A PROPER OUTWARD SLOPE AWAY FROM THE ENTRANCE TO PREVENT RAINWATERINGRESS INTO THE LABORATORY. WORKS SHALL INCLUDE SURFACE PREPARATION,REPAIR AND LEVELING, APPROVED EPOXY FLOOR C OATING MATCHING THE EXISTINGFINISH, SEALING OF JOINTS/INTERFACES WITH SUITABLE WEATHER-RESISTANTSEALANT, PROPER CORNER/EDGE FINISHIN G, MAKING GOOD ADJACENT SURFACES,AND ALL NECESSARY MATERIALS AND ACCESSORIES TO COMPLETE THE WORKS.SIZE: 1.5M X 2.25M	3	M2				
8		ITEM-00001	1.8) SOLAR LAB & AGING LAB: REMOVE EXISTING DAMAGED SEALANT AROUND DUCTPENETRATIONS AND PROVIDE AN APPROVED EXTERNAL-GRADE WATERPROO	22	M				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			F SEALINGSYSTEM, INCLUDING SURFACE/JOINT PREPARATION, SUITABLE BACKING/FILLERMATERIAL, TREATMENT OF JOINTS, CORNERS AND PENETRATIONS , AND APPLICATIONOF COMPATIBLE WATER, WEATHER, UV AND ALKALI-RESISTANT SEALANT, COMPLETETO PREVENT RAINWATER INGRESS.						
9		ITEM-00001	1.9) SOLAR LAB: SUPPLY AND APPLY WATERPROOF SEALANT TO MEP DUCT/SHAFTJOINTS, INCLUDING NECESSARY JOINT TREATMENT, OVERLAPS, REINFORC ING FIBERMESH AND APPROVED WATERPROOFING SEALANT/COATING, COMPLETE TO PREVENTRAINWATER LEAKAGE AND AS PER APPROVED SPECIFICATIONS.	48	M				
10		ITEM-00001	1.10) SOLAR LAB: REMOVE AND CAREFULLY REINSTATE EXISTING METALFLASHING/COVER AS REQUIRED, REMOVE DAMAGED SEALANT, CLEAN AND PREPARET HE EXPANSION JOINT, CARRY OUT NECESSARY REPAIRS, AND PROVIDE ANAPPROVED FLEXIBLE WATERPROOF MOVEMENT-JOINT SEALING SYSTEM, INCLUDING	8	M				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026
REQ No : 1032605556
REQ TITLE : Rectification of Rain Water L
DELIVERY LOCATION
CLOSING DATE : 19.11.2026
CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			BACKING MATERIAL/PRIMER WHERE REQUIRED, COMPLETE TO PREVENT WATERINGRESS.						
11		ITEM-00001	1.11) GF CHEMICAL LAB & OTHER LOCATIONS: REMOVE EXISTING DAMAGED SEALANTAND PROVIDE APPROVED EXTERNAL-GRADE WATERPROOF SEALANT TO ME P PIPEPENETRATIONS THROUGH GLAZING AND WALLS, INCLUDING CLEANING, SURFACEPREPARATION, NECESSARY REPAIRS, BACKING MATERIAL/PRIMER WHE RE REQUIRED,AND COMPATIBLE SEALANT, COMPLETE TO PREVENT WATER INGRESS.	1	NO				
12		ITEM-00001	1.12) SITTING AREA: SUPPLY AND INSTALL 15 MM HIGH × 1,000 MM LONGAPPROVED WEATHER-RESISTANT THRESHOLD/WATER BARRIER AT THE EXTERNALA LUMINIUM DOOR TO MINIMIZE RAINWATER INGRESS, INCLUDING NECESSARYFIXING, SEALING AND FINISHING, COMPLETE.	1	NO				
13		ITEM-00001	1.13) PUMP ROOM: REMOVE AND REINSTATE EXISTING METAL FLASHING/COVER ASREQUIRED, REMOVE DAMAGED SEALANT AROUND THE REMOVABLE CONCRETE	28	M				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SLAB,CLEAN AND PREPARE THE CONSTRUCTION JOINT, CARRY OUT NECESSARY REPAIRS,AND PROVIDE AN APPROVED FLEXIBLE WATERPROOF JOINT SEALIN G SYSTEM,INCLUDING BACKING MATERIAL/PRIMER WHERE REQUIRED, COMPLETE TO PREVENTRAINWATER INGRESS.						
14		ITEM-00001	1.14) LABS & OTHER AREAS: SUPPLY AND INSTALL CURVED WEATHERPROOF DOORCANOPY/SHADE, APPROXIMATELY 2.0 M × 1.0 M, ABOVE EXTERNAL DOORS TOPREVENT DIRECT RAINWATER INGRESS, INCLUDING SUPPORTING FRAME, WATERPROOFCOVERING, BRACKETS, FIXINGS, CONNECTIONS, SEALING, PROPER OUTWARDSLOPE/DRAINAGE, ALIGNMENT AND ALL ACCESSORIES, COMPLETE AS PER APPROVEDSPECIFICATIONS.	9	NO				
15		ITEM-00001	1.15) GROUND FLOOR CORRIDOR: SUPPLY AND INSTALL GYPSUM GRID CEILING ANDREPAIR EXISTING BULKHEAD, INCLUDING NECESSARY SUPPORTING FRAM EWORK,ANGLES, FIXINGS, MAKING GOOD AND	18	M2				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332602934

DATE : 13.11.2026

REQ No : 1032605556

REQ TITLE : Rectification of Rain Water L

DELIVERY LOCATION

CLOSING DATE : 19.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			FINISHING, COMPLETE AS PER APPROVEDSPECIFICATIONS AND PROJECT REQUIREMENTS.						
16		ITEM-00001	1.16) ANY OTHER ITEMS OF WORK NOT INCLUDED IN THE ABOVE ITEMS, BUTREQUIREMENT OF WHICH IS REQUIRED AS PER DRAWINGS, SPECIFICATIONS A NDSITE REQUIREMENTS. TENDERER SHALL CLEARLY DESCRIBE THE ITEMS AND QUOTEWITH UNIT PRICES. (IT WILL BE ASSUMED THAT THE TENDERER#S OF FER FULLYCOMPLIES WITH THE SPECIFICATION/RELEVANT STANDARDS IN ALL RESPECTSUNLESS ANY ADDITIONAL WORKS ARE LISTED UNDER THIS ITEM)1. 2.	1	LS				

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

Rectification of Rain Water Leakages at R <(>&<)> D Centre.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602934
DATE	: 13.11.2026
REQ No	: 1032605556
REQ TITLE	: Rectification of Rain Water L
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

Contact: Muhammad Farooq Nasim/ 050 3724975
Site Visit: 18.Nov.2026 @10:00 AM
Payment: 100% work completion/ Retention: 5%

STANDARD TERMS & CONDITIONS

1) RFQ Document Disclaimer: The PDF version of this Request for Quotation (RFQ) is provided for convenience only and contains a summary of key information. It does not include all technical details, requirements, or specifications. Bidders must refer to the complete system documentation and all referenced materials to obtain full and accurate information necessary for preparing their proposals.

2) Prices should be 'DDP' delivery duty paid at DEWA stores.

3) Quotation to be submitted only in local currency U.A.E Dirhams

4) DEWA Standard Payments: Payment will be made within 30 days from the date the Supplier/Contractor submits a complete and accurate invoice, together with all required supporting documents, subject to the material and/or services having been duly accepted.

5) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

6) The offered product and/or services in the Quotation, shall be confirming and in accordance with DEWA Energy Management Policy & EnMS Manual.

7) Confidentiality Clause: The Supplier/Service Provider shall treat all information and data (excluding open data) contained in the Purchase Order or obtained by the Supplier/Service Provider in connection with the execution of Works as proprietary and strictly confidential. In particular, the Supplier/ Service Provider shall not publish or disclose any data or information including but not limited to personally identifiable information, government data, project details, specifications, drawings or photographs concerning the Works to any third parties without the prior written consent of the Employer. If

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602934
DATE	: 13.11.2026
REQ No	: 1032605556
REQ TITLE	: Rectification of Rain Water L
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

the Supplier/Service Provider is obligated to obtain NOCs / Permits /Permissions for the Project from Government agencies as per the terms and scope of the Contract, the Supplier/Service Provider shall submit only the specific data required for the purpose to the authorized team of the agency, through their prescribed channel / system, subject to information security requirements. The Supplier/Service Provider shall comply with all the applicable data protection laws and regulations.

8)Data Privacy, Security and Sharing:
a) Third-party shall handle DEWA data in accordance with all applicable laws, regulations, and DEWA policies.
b) DEWA data shall not be shared outside UAE, in line with DESC ISR requirements.
c) DEWA's Non-Disclosure Agreement (NDA) and External Party Acknowledgment (EPA) shall be signed by the third-party and their sub-contractors who handle DEWA data prior to the contract commencement.
d) DEWA reserves the right to withhold data from third parties if deemed sensitive.
e) Access to data must be restricted to authorized, named third-party employees only and DEWA must be informed of any changes in employment status of those with access.
f) Third party shall not disclose, transfer or share any DEWA data with other third parties (government, semi government, private) without obtaining DEWA#s authorized data owner written approval.
g) Upon the completion/ termination of the agreement the external party shall securely delete all DEWA#s data in their custody/ control including the backup and provide written confirmation and evidence to DEWA upon the data deletion completion as per agreed data disposal process, this is to address risk of data remanence.

9) Liquidated Damages for PO total value in excess of AED 50,000:
If the Contractor/Supplier delays or fails to deliver, fails to commence or perform the services, DEWA has the right to deduct an amount equal to 1.25% per day/week of the total PO fee for the services/supplies delayed, not performed or not delivered, subject to a cap of 10% of the total PO fee without recourse to any judicial proceedings, as compensation for the delay or failure to perform. If the deducted amount exceeds 10% of the total PO fee, without prejudice to any of DEWA's rights under the applicable law, DEWA shall be entitled to terminate the PO immediately without the need for any notice or judicial proceedings against the defaulting Supplier, and without the need to prove the damage.

10) Indemnity: The Supplier shall indemnify DEWA from and against all claims, damages, costs and liabilities brought by any third party against DEWA arising out of or in connection with any of acts or omissions of the Supplier/Contractor, or any failure to perform its obligations under this PO.

11) Dispute Resolution: Any dispute arising out of or in connection with this PO shall be settled through mutual good faith negotiation and understanding between the Parties: Failing amicable settlement,

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602934
DATE	: 13.11.2026
REQ No	: 1032605556
REQ TITLE	: Rectification of Rain Water L
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

the dispute shall finally be referred to the courts having appropriate jurisdiction in the Emirate of Dubai.

12) Intellectual Property Rights: The Supplier/Contractor shall not use DEWA's intellectual property, including logos, trademarks, service marks, trade names, service names, and brand names, whether in a press release or otherwise, without obtaining DEWA's prior written consent. All intellectual property rights in the deliverables created or developed, under this PO, shall be solely owned by DEWA.

13) Assignment and Transfer: The Supplier/Contractor shall not assign this PO or any part thereof without the prior written consent of DEWA. Such consent shall not relieve the Contractor of any of its obligations or duties under this PO.

14) Force Majeure: If either party is affected by a Force Majeure event, it will promptly notify the other party of the nature and extent thereof. Neither party will be deemed to be in breach of this PO, by reason of any delay or non-performance, of any of its obligations hereunder, due to any Force Majeure event of which it has notified the other party. The time for performance of these obligations will be extended accordingly as may be fair and reasonable in the circumstances. Provided always that if the duration of such delay or impediment exceeds thirty (30) days, either party may give a fifteen (15) working days' notice to terminate a specific item or the PO in its entirety.

15) Certificate of Conformity for Green Materials and Services Specifications: The Bidder shall, wherever applicable, provide a Certificate of conformity issued by accredited body/ laboratory as proof of compliance with the applicable green materials, services and specifications.

16) Taking Over Certificate: TOC shall be issued only after full delivery or completion of the service or deliverables. TOC will be issued conditionally ("conditional TOC") with the reasonable guarantee/observation in case of any defects after delivery or completion of the PO.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332602934
DATE	: 13.11.2026
REQ No	: 1032605556
REQ TITLE	: Rectification of Rain Water L
DELIVERY LOCATION	
CLOSING DATE	: 19.11.2026
CLOSING TIME	: 10:00:00

SUPPLIER'S REMARKS :

SUPPLIER'S SIGNATURE AND STAMP

DISCLAIMER : THIS IS A SYSTEM GENERATED DOCUMENT , DOSEN'T NEED SIGNATURE.