REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	TECHNICAL AND GENERAL SPECIFICATIONS -OUTSOURCING WORK. L STATION PHASE I, JEBEL ALINAME OF WORK:#HRSG DIVERTER DAMPER HYDRAULIC ACC UMUALTOR OVERHAULING,TESTING, CYLINDER & PISTON REFURBISHMENT (WO 511386022).PERIOD OF WORK:##10 DAYS AFTER RECEIVING POQUANTITY:##0 1 PIECESCOPE OF WORK 1 # ACCUMULATOR OVERHAULING, SEALS REPLACEMENT ANDTESTING.·#THE CONTRACTOR SHALL VISIT THE SITE AND BE FULLY FA MILIAR WITH THEWORK SCOPE, PLANT ACCESS, FACILITIES, COMPLEXITIES, SAFETY MEASURESETC., BEFORE HE SUBMITS HIS BID. QUOTED PRICE SHAL L BE FINAL AS PERACTIVITIES SPECIFIED IN BELOW SCOPE & DEWA WILL NOT ACCEPT ANY CLAIM FOREXTRAS BEYOND THE ORDER VALUE DURING AND AF TER THE EXECUTION OF WORK.·#THE CONTRACTOR SHALL HAVE EXPERIENCE RELATED TO SIMILAR ACTIVITIES.RELEVANT DOCUMENTS TO	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			BE SUBMITTED TO DEWA.·#AFTER RECEIVING PO, COLLECT THE ACCUMULATOR AND REPAIR KIT FROM DEWAL1 STATION, JEBEL ALI WITHIN 24 HOURS OF NOTICE.·#DISMAN TLE THE ACCUMULATOR BY REMOVING THE HYDRAULIC CAP AND GAS CAPS.·#CYLINDER - CHECK FOR LONGITUDINAL SCORING, CORROSION/PITTING, GALLI NGAND ABNORMAL WEAR IN THE CYLINDER (ACCUMULATOR BODY). MEASURE ID,OVALITY AND TAPER AND CHECK SURFACE FINISH.·#PISTON & CAPS - MEAS URE THE CRITICAL ODS AND INSPECT THE SEAL ANDWEAR-RING GROOVES.·#LOOK ESPECIALLY FOR SCORING THAT INDICATES THE PTFE GLIDE RING HASF AILED OR WORN THROUGH.·#PREPARE INITIAL INSPECTION REPORT INCLUDING PISTON DIAMETER, CYLINDERBORE DIAMETER AND WEAR DIMENSIONS WITH PHOTOS AND SHARE WITH DEWA.·#HONING OF CYLINDER BORE AS REQUIRED.·#DO NOT CHROME						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THE PISTON AUTOMATICALLY. CHROME PLATING IS JUSTIFI EDONLY IF DIMENSIONAL RESTORATION IS REQUIRED AND IF DEWA AGREED.·#AFTER DEWA#S CLEARANCE, CHROMING SHALL BE DONE UNDER SCOPE 2 (ONL Y IFREQUIRED)·#DEEP CLEAN THE COMPONENTS AND POLISH THE PISTON.·#ASSEMBLE THE ACCUMULATOR USING THE OEM REPAIR KIT SUPPLIED BY DEWA(FREE SUPPLY)·#HYDRAULIC PRESSURE TESTING OF THE ACCUMULATOR AT 200 BAR INACCORDANCE WITH THE OEM RECOMMENDATION. ACCUMULATOR SHALL B E TESTED ONBOTH OIL AND NITROGEN SIDES. DEWA REPRESENTATIVE RESERVES THE RIGHT TOWITNESS THE TESTING. OIL TO BE USED FOR THE TESTING IS QUINTOLUBRIC;VISCOSITY RATING:888-68; KINEMATIC VISCOSITY AT 40 C IS 68 MM²/S FORCYLINDER TESTING.·#GRAPH RECORDER SHALL BE USED DURING THE TEST, AND PRESSURE DROP						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SHALLBE AS PER OEM RECOMMENDATION/STANDARD INDUSTRY PRACTICE.·#ALL DIMENSIONS AFTER REPAIR SHALL BE RESTORED TO THE ORIGINAL OEMDIMENSIONS AND TOLERANCES.·#CONTRACTOR SHALL PROVIDE DIMENSIONAL INSPECTION REPORTS BEFORE ANDAFTER REFURBISHMENT.·#PROVIDE PRESSURE TEST CERTIFICATE, REFURBISHMENT REPORT AND FIVE (05)YEAR WARRANTY CERTIFICATE.·#RETURN THE TESTED A CCUMULATOR TO DEWA WITH PROPER COVERING TO KEEPTHE ACCUMULATOR AT STORE.·#SUBMISSION OF FINAL WORK COMPLETION REPORT WITH DIMENSIONA L REPORTS,PRESSURE TEST CERTIFICATES·#ACCUMULATOR DETAILS GIVEN BELOW;ACCUMULATOR, PISTON ACCUMULATOR COMPLETE ASSEMBLY, MODEL NUMBE R:A7L3465D412E, MAXIMUM ALLOWABLE WORKING PRESSURE: 3000 PSI AT 400 DEG F,MINIMUM DESIGN METAL TEMPERATURE: 20 DEG AT 3000						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			PSI, YEAR OFMANUFACTURING: 2002, CHARGE PRESSURE: 1000 PSI, SERIAL NUMBER: 36718,36721, MANUFACTURER: PARKER HYDRAULICS. CERTIFIED BY ROCKFO RD, IL,SUPPLIER: BLAC INC, FOR HRSG DIVERTER DAMPER HPU.CONTRACTOR SCOPE OF SUPPLY·#TEST BENCH AND ACCESSORIES.·#LIFTING EQUIPMENT·# ALL THE REQUIRED TOOLS & MANPOWER TO CARRY OUT THE SCOPE.DEWA SCOPE OF SUPPLY·#ACCUMULATOR REPAIR KIT (OEM)·#FORKLIFTWARRANTY·#IN CA SE OF ANY DAMAGE/DEFECT OF ANY EQUIPMENT HAPPENS DURING THISCONTRACT, THE CONTRACTOR SHALL ATTEND AND CARRY OUT THE NECESSARY REPAIR WORK AND RECTIFY THE DEFECT WITHIN SHORT PERIOD WITHOUT AFFECTING THEPRODUCTION OF ELECTRICITY AND WATER.·#CONTRACTOR SHALL OFFER MI NIMUM OF 5 YEARS WARRANTY FOR THE WORKCARRIED OUT. ANY LEAKAGE,						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			MALFUNCTION, ABNORMAL WEAR, CHROME PLATINGFAILURE, WORKMANSHIP DEFEC T OF CYLINDER PERFORMANCE ISSUE OBSERVEDDURING THE WARRANTY PERIOD SHALL BE RECTIFIED BY THE CONTRACTOR AT NOADDITIONAL COST TO DEWA MOBILIZATION TIME1-DAY ADVANCE NOTICE						
2		ITEM-00001	TECHNICAL AND GENERAL SPECIFICATIONS -OUTSOURCING WORK. L STATION PHASE I, JEBEL ALINAME OF WORK:#HRSG DIVERTER DAMPER HYDRAULIC ACC UMUALTOR OVERHAULING,TESTING, CYLINDER & PISTON REFURBISHMENT (WO 511386022).PERIOD OF WORK:##10 DAYS AFTER RECEIVING POQUANTITY:##0 1 PIECESCOPE OF WORK 2 # HARD CHROME PLATING (CHROMING) OF ACCUMULATOR PISTONTHIS SCOPE SHALL BE CARRIED OUT ONLY UPON APPROVAL FROM DEWA BASED ONTHE INSPECTION FINDINGS DURING REFURBISHMENT OF THE HYDRAULICACCUMULATOR UNDER SCOPE OF WORK 1.·#FOLLOWING DISMANTLING	1	EA				

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			AND INSPECTION OF THE HYDRAULIC ACCUMULATOR,THE CONTRACTOR SHALL CONDUCT A DETAILED DIMENSIONAL AND VISUALINSPECTION OF THE PISTON AND SUBMIT AN INSPECTION REPORT WITHPHOTOGRAPHS TO DEWA FOR REVIEW AND APPROVAL.·#THE CONTRACTOR SHALL MEASURE AND RECORD:O#PISTON D IAMETER AT MULTIPLE LOCATIONS.O#SURFACE CONDITION.O#STRAIGHTNESS/RUNOUT.O#CHROM E COATING CONDITION.O#EXTENT OF PITTING, SCRATCHES, S CORING, CORROSION, AND WEAR.·#IF THE PISTON CHROME SURFACE IS FOUND DAMAGED AND IS BEYONDACCEPTABLE CONDITION, THE EXISTING CHROME L AYER SHALL BE REMOVEDCOMPLETELY BY APPROVED MACHINING/GRINDING METHODS.·#THE PISTON SHALL BE VISUALLY INSPECTED FOR CRACKS, MECHANIC AL DAMAGE,CORROSION AND PITTING.·#ANY ABNORMALITIES SHALL BE REPORTED TO DEWA BEFORE PROCEEDING.·#ANY DEFECTS FOUND						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			SHALL BE REPORTE D TO DEWA FOR REVIEW BEFOREPROCEEDING WITH REPAIR.·#THE PISTON BASE MATERIAL SHALL BE MACHINED AND PREPARED FOR HARDCHROME PLATING.· #HARD CHROME PLATING SHALL BE CARRIED OUT AT AN APPROVED FACILITYUSING INDUSTRIAL HARD CHROME PLATING PROCESS.·#THE EXISTING DAMAGED CHROME PLATING SHALL BE REMOVED, AND NEW HARDCHROME PLATING SHALL BE APPLIED AS REQUIRED TO RESTORE THE PISTON TO THEORIGINAL OEM D IMENSIONS. THE FINAL CHROME THICKNESS SHALL BE SUFFICIENTTO ACHIEVE THE REQUIRED FINISHED DIMENSIONS. CONTRACTOR SHALL SUBMITCHROME PLATING THICKNESS MEASUREMENTS AND INSPECTION REPORTS TO DEWA.·#THE CHROME PLATING SHALL BE UNIFORM, FREE FROM CRACKS, PEELING,BLIST ERING, PIN HOLES, BURNS, PITS, OR OTHER COATING DEFECTS.·#AFTER CHROME PLATING,						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THE PISTON SHALL BE PRECISION GROUND ANDPOLISHED TO ACHIEVE:O#ORIGINAL OEM DIAMETER.O#SMOOTH SURFACE FINISH.O#MIRROR FINISH SUITABLE FOR HYDRAULIC SEALING APPLICATIONS.·#SURFACE ROUGHN ESS MEASUREMENT RECORDS SHALL BE SUBMITTED TO DEWA.·#CONTRACTOR SHALL SUBMIT THE FOLLOWING REPORTS TO DEWA:O#PRE-CHROMING DIMENSIONA L INSPECTION REPORT.O#CHROME PLATING PROCESS REPORT.O#FINAL DIMENSIONAL INSPECTION REPORT.O#SURFACE ROUGHNESS REPORT.O#STRAIGHTNESS/ RUNOUT REPORT.O#PHOTOGRAPHIC RECORDS BEFORE, DURING AND AFTER REPAIR.O#ALL DIMENSIONS AFTER REPAIR SHALL BE RESTORED TO THE ORIGINAL OEMDIMENSIONS AND TOLERANCES.·#CONTRACTOR SHALL PROVIDE DIMENSIONAL INSPECTION REPORTS BEFORE ANDAFTER REFURBISHMENT.·#FINAL DIMENS IONS SHALL BE VERIFIED BY CONTRACTOR						

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			BEFORE ASSEMBLY OFTHE HYDRAULIC ACCUMULATOR AND INFORM DEWA (IF REQUIRED DEWAREPRESENTATIVE WIL L VISIT TO CONTRACTOR#S WORKSHOP).·#THE REFURBISHED PISTON SHALL BE ASSEMBLED BACK INTO THE HYDRAULICACCUMULATOR UNDER SCOPE OF WORK #1.·#HYDROSTATIC/PRESSURE TESTING OF THE COMPLETE HYDRAULIC ACCUMULATORSHALL BE CARRIED OUT AS SPECIFIED IN SCOPE OF WORK #1 AFTER COMPLETIONOF CHROME PLATING AND REASSEMBLY.·#CONTRACTOR SHALL PROVIDE A FIVE (05) YEAR WARRANTY FOR THE HARDCHROME PLATING WORKMANSH IP AGAINST PEELING, FLAKING, BLISTERING ANDABNORMAL WEAR UNDER NORMAL OPERATING CONDITIONS.·#THE CONTRACTOR SHALL PROVIDE A WARRANTY CERTIFICATE TOGETHER WITH ALLINSPECTION AND TESTING RECORDS.·#ALL CONSUMABLES, MACHINING, GRINDING, CHROME PLATING, POLISHING,INSPE					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			CTION EQUIPMENT, TRANSPORTATION AND ASSOCIATED ACTIVITIES REQUIREDFOR COMPLETION OF THE WORK SHALL BE IN CONTRACTOR'S SCOPE.CONTRACT OR SCOPE OF SUPPLY·#TEST BENCH AND ACCESSORIES.·#LIFTING EQUIPMENT·#ALL THE REQUIRED TOOLS & MANPOWER TO CARRY OUT THE SCOPE.DEWA SC OPE OF SUPPLY·#ACCUMULATOR REPAIR KIT (OEM)·#FORKLIFTWARRANTY·#IN CASE OF ANY DAMAGE/DEFECT OF ANY EQUIPMENT HAPPENS DURING THISCONT RACT, THE CONTRACTOR SHALL ATTEND AND CARRY OUT THE NECESSARY REPAIRWORK AND RECTIFY THE DEFECT WITHIN SHORT PERIOD WITHOUT AFFECTIN G THEPRODUCTION OF ELECTRICITY AND WATER.·#CONTRACTOR SHALL OFFER MINIMUM OF 5 YEARS WARRANTY FOR THE WORKCARRIED OUT. ANY LEAKAGE, MALFUNCTION, ABNORMAL WEAR, CHROME PLATINGFAILURE, WORKMANSHIP DEFECT OF CYLINDER PERFORMANCE ISSUE					

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER : 2332603015

DATE : 19.11.2026

REQ No : 1032605775

REQ TITLE : 1032605775 HRSG DIVERTER

DELIVERY LOCATION

CLOSING DATE : 25.11.2026

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OBSERVEDDURING THE WARRANTY PERI OD SHALL BE RECTIFIED BY THE CONTRACTOR AT NOADDITIONAL COST TO DEWAMOBILIZATION TIME1-DAY ADVANCE NOTICE						

TOTAL AMOUNT IN WORDS:

TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

HRSG DIVERTER DAMPER HYDRAULIC ACCUMUALTOR OVERHAULING, TESTING,CYLINDER and PISTON REFURBISHMENT. Contact Person - basil.joy@dewa.gov.ae

STANDARD TERMS & CONDITIONS

1) RFQ Document Disclaimer: The PDF version of this Request for Quotation (RFQ) is provided for convenience only and contains a summary of key information. It does not include all technical details, requirements, or specifications. Bidders must refer to the complete system documentation and all referenced materials to obtain full and accurate information necessary for preparing their proposals.

2) Prices should be 'DDP' delivery duty paid at DEWA stores.

3) Quotation to be submitted only in local currency U.A.E Dirhams

4) DEWA Standard Payments: Payment will be made within 30 days from the date the Supplier/Contractor submits a complete and accurate invoice, together with all required supporting documents, subject to the material and/or services having been duly accepted.

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332603015
DATE	: 19.11.2026
REQ No	: 1032605775
REQ TITLE	: 1032605775 HRSG DIVERTER
DELIVERY LOCATION	
CLOSING DATE	: 25.11.2026
CLOSING TIME	: 10:00:00

5) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.

6) The offered product and/or services in the Quotation, shall be confirming and in accordance with DEWA Energy Management Policy & EnMS Manual.

7) Confidentiality Clause: The Supplier/Service Provider shall treat all information and data (excluding open data) contained in the Purchase Order or obtained by the Supplier/Service Provider in connection with the execution of Works as proprietary and strictly confidential. In particular, the Supplier/ Service Provider shall not publish or disclose any data or information including but not limited to personally identifiable information, government data, project details, specifications, drawings or photographs concerning the Works to any third parties without the prior written consent of the Employer. If the Supplier/Service Provider is obligated to obtain NOCs / Permits /Permissions for the Project from Government agencies as per the terms and scope of the Contract, the Supplier/Service Provider shall submit only the specific data required for the purpose to the authorized team of the agency, through their prescribed channel / system, subject to information security requirements. The Supplier/Service Provider shall comply with all the applicable data protection laws and regulations.

8)Data Privacy, Security and Sharing:
a) Third-party shall handle DEWA data in accordance with all applicable laws, regulations, and DEWA policies.
b) DEWA data shall not be shared outside UAE, in line with DESC ISR requirements.
c) DEWA's Non-Disclosure Agreement (NDA) and External Party Acknowledgment (EPA) shall be signed by the third-party and their sub-contractors who handle DEWA data prior to the contract commencement.
d) DEWA reserves the right to withhold data from third parties if deemed sensitive.
e) Access to data must be restricted to authorized, named third-party employees only and DEWA must be informed of any changes in employment status of those with access.
f) Third party shall not disclose, transfer or share any DEWA data with other third parties (government, semi government, private) without obtaining DEWA#s authorized data owner written approval.
g) Upon the completion/ termination of the agreement the external party shall securely delete all DEWA#s data in their custody/ control including the backup and provide written confirmation and evidence to DEWA upon the data deletion completion as per agreed data disposal process, this is to address risk of data remanence.

9) Liquidated Damages for PO total value in excess of AED 50,000:
If the Contractor/Supplier delays or fails to deliver, fails to commence or perform the services, DEWA has the right to deduct an amount equal to 1.25% per day/week of the total PO fee for the

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332603015
DATE	: 19.11.2026
REQ No	: 1032605775
REQ TITLE	: 1032605775 HRSG DIVERTER
DELIVERY LOCATION	
CLOSING DATE	: 25.11.2026
CLOSING TIME	: 10:00:00

services/supplies delayed, not performed or not delivered, subject to a cap of 10% of the total PO fee without recourse to any judicial proceedings, as compensation for the delay or failure to perform. If the deducted amount exceeds 10% of the total PO fee, without prejudice to any of DEWA's rights under the applicable law, DEWA shall be entitled to terminate the PO immediately without the need for any notice or judicial proceedings against the defaulting Supplier, and without the need to prove the damage.

10) Indemnity: The Supplier shall indemnify DEWA from and against all claims, damages, costs and liabilities brought by any third party against DEWA arising out of or in connection with any of acts or omissions of the Supplier/Contractor, or any failure to perform its obligations under this PO.

11) Dispute Resolution: Any dispute arising out of or in connection with this PO shall be settled through mutual good faith negotiation and understanding between the Parties: Failing amicable settlement, the dispute shall finally be referred to the courts having appropriate jurisdiction in the Emirate of Dubai.

12) Intellectual Property Rights: The Supplier/Contractor shall not use DEWA's intellectual property, including logos, trademarks, service marks, trade names, service names, and brand names, whether in a press release or otherwise, without obtaining DEWA's prior written consent. All intellectual property rights in the deliverables created or developed, under this PO, shall be solely owned by DEWA.

13) Assignment and Transfer: The Supplier/Contractor shall not assign this PO or any part thereof without the prior written consent of DEWA. Such consent shall not relieve the Contractor of any of its obligations or duties under this PO.

14) Force Majeure: If either party is affected by a Force Majeure event, it will promptly notify the other party of the nature and extent thereof. Neither party will be deemed to be in breach of this PO, by reason of any delay or non-performance, of any of its obligations hereunder, due to any Force Majeure event of which it has notified the other party. The time for performance of these obligations will be extended accordingly as may be fair and reasonable in the circumstances. Provided always that if the duration of such delay or impediment exceeds thirty (30) days, either party may give a fifteen (15) working days' notice to terminate a specific item or the PO in its entirety.

15) Certificate of Conformity for Green Materials and Services Specifications: The Bidder shall, wherever applicable, provide a Certificate of conformity issued by accredited body/ laboratory as proof of compliance with the applicable green materials, services and specifications.

16) Taking Over Certificate: TOC shall be issued only after full delivery or completion of the service or deliverables. TOC will be issued conditionally ("conditional TOC") with the reasonable

REQUEST FOR QUOTATION
LOCAL PURCHASE SECTION

RFQ NUMBER	: 2332603015
DATE	: 19.11.2026
REQ No	: 1032605775
REQ TITLE	: 1032605775 HRSG DIVERTER
DELIVERY LOCATION	
CLOSING DATE	: 25.11.2026
CLOSING TIME	: 10:00:00

guarantee/observation in case of any defects after delivery or completion of the PO.

SUPPLIER'S REMARKS :

SUPPLIER'S SIGNATURE AND STAMP

DISCLAIMER : THIS IS A SYSTEM GENERATED DOCUMENT , DOSEN'T NEED SIGNATURE.