



RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
1		ITEM-00001	TECHNICAL AND GENERAL SPECIFICATIONS,	1	LS				
			OUTSOURCING WORK K STATION PHASE II, JEBEL						
			ALI NAME OF WORK: SCOPE OF WORK FOR HP/MP						
			PCV P						
			R TUBE REPLACEMENT (VALVE INLET SIZE DN8# &						
			OUTLET DN 12#) DURATION OF WORK: 4 DAYS						
			(TENTATIVE PERIOD OF WORK # AFTER AWARDING						
			THE						
			PO TO FIRST QUARTER OF 2024) NOTICE PERIOD						
			# 1 DAY SCOPE OF WORK: .#THE CONTRACTOR						
			SHALL VISIT THE SITE AND MAKE HIMSELF FULLY						
			FAMILIAR WITH THE WORK SCOPE, PLANT ACCESS,						
			FACILITIES, COMPLEXITIES, SAFETY MEASURES,						
			ERECTION PROCEDURES, NUMBER OF WELDS						
			ETC., BE						
			FORE HE SUBMITS HIS BID. #PARTY SHALL SUBMIT						
			ITP ALONG WITH WPS, LIFTING PLAN AND						
			ERECTION PLAN AFTER GETTING PO AND BEFORE						
			COMMENC						
			ING OF WORK#TO GET A PTW, HWP						
			CONTRACTOR HAS TO SUBMIT RISK ASSESSMENT						
			FORMS AND METHOD STATEMENT PRIOR TO						
			START THE WORK#CHEC						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			K CONDITION SUITABLE TO CARRY OUT WORK.						
			CONDUCT SITE SURVEY AND SAFETY INSPECTION						
			TO ASSESS THE WORKING ENVIRONMENT. ·#A						
			SAFETY MEET						
			ING WILL BE HELD TO EVALUATE THE RISK						
			INVOLVED IN METHODS TO BE USED. RISK						
			ASSESSMENT AND TOOLBOX TALK TO BE GIVEN						
			TO THE EMPLOYEES.						
			·#PARTY SHALL MOBILIZE THE LABOR,						
			EQUIPMENT, TOOLS, ETC. IMMEDIATELY AFTER						
			DEWA NOTIFICATION. PARTY SHALL READY TO						
			START THE WORK W						
			ITH THREE-DAYS ADVANCE NOTIFICATION. #ALL						
			LIFTING AND POWER TOOLS SHALL BE TESTED						
			AND TEST CERTIFICATE TO BE PROVIDED TO						
			DEWA. #PA						
			RTY SHALL VERIFY THAT SCAFFOLDS ARE SAFE TO						
			WORK AND VALID SCAFFOLDING TAGS ARE						
			PROVIDED BEFORE USING ANY SCAFFOLDING						
			(SCAFFOLDING B						
			Y DEWA)#INSPECT THE EXISTING INNER, MIDDLE AND OUTER PR TUBES INCLUDING END PLATE AND						
			COMPARE THE MEASUREMENTS WITH NEWLY						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			PROVIDE						
			D PR TUBES#CUT AND REMOVE 2# DE-SUPER						
			HEATER SPRAY WATER LINE (F22 MATERIAL)						
			-#CUT AND REMOVE 12# VALVE BODY OUTLET (
			MATERIAL F						
			22) ·#AFTER VERIFICATION OF EXISTING PR TUBE						
			DIMENSIONS WITH NEWLY PROVIDED PR TUBES,						
			REMOVE THE EXISTING INNER, OUTER PR TUBES						
			INCL						
			UDING END PLATE WITHOUT DAMAGING THE						
			VALVE BODY SURFACE#FIT UP THE JOINT						
			BETWEEN NEW INNER PR TUBE AND NEW END						
			PLATE. ·#AFTER DEW						
			A & OEM CLEARANCE, WELDING OF INNER PR						
			TUBE WITH END PLATE JOINT AS PER APPROVED						
			WPS#FIT UP THE JOINT BETWEEN NEW OUTER						
			PR TUBE A						
			ND NEW END PLATE. ·#AFTER DEWA & OEM						
			CLEARANCE, WELDING OF OUTER PR TUBE WITH						
			END PLATE JOINT AS PER APPROVED WPS#NDT						
			AND PWHT OF						
			INNER PR TUBE TO END PLATE JOINT. #SURFACE						
			PREPARATION OF VALVE BODY FOR INNER AND						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			OUTER PR TUBE JOINTS#IN CASE OF						
			DIMENSIONAL						
			VARIATIONS DUE TO EROSION OF VALVE BODY						
			SURFACE, THE SAME SHALL BE RECTIFIED BY THE						
			CONTRACTOR. (FILL UP/BUTTERING TO ACQUIRE						
			THE DE						
			SIRED DIMENSIONS) :#UPON SURFACE FINISHING						
			OF BOTH PR TUBE AND VALVE BODY, FIT UP THE						
			JOINT BETWEEN OUTER PR TUBE AND VALVE						
			BODY. CH						
			ECK THE GUIDE LENGTH AND CLEARANCE OF PR						
			TUBE INSIDE THE END PLATE#AFTER DEWA						
			CLEARANCE, WELDING OF PR TUBE TO VALVE						
			BODY JOINT A						
			S PER APPROVED WPS#NDT OF COMPLETED						
			WELDING JOINT FOLLOWED BY PWHT .#VALVE						
			BODY OUTER SURFACE FINISH, FIT UP VALVE						
			BODY OUTER JOI						
			NT. JOINT FIT UP SHALL WITNESS BY DEWA.						
			·#UPON DEWA APPROVAL, WELDING OF VALVE						
			BODY OUTER AS PER APPROVED WPS#NDT OF						
			COMPLETED WE						
			LDING JOINT FOLLOWED BY PWHT .#SPRAY WATER						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			LINE SURFACE FINISH, FIT UP SPRAY WATER LINE						
			WELD JOINT. FIT UP SHALL WITNESS BY DEWA .#U						
			PON DEWA APPROVAL, WELDING OF SPRAY						
			WATER LINE AS PER APPROVED WPS#NDT OF						
			COMPLETED WELDING JOINT FOLLOWED BY PWHT.						
			·#ANY INSULAT						
			ION/CLADDING SHEET REMOVAL AND RE FIXING IF						
			REQUIRED DURING THE REPLACEMENT, SAME						
			SHALL BE UNDER CONTRACTOR SCOPE#AFTER						
			COMPLETIO						
			N OF ABOVE SCOPE OF WORK, JOINT INSPECTION						
			WITH DEWA ENGINEER. #AFTER FINAL						
			CLEARANCE FROM DEWA, INSTALL BACK						
			INSULATION CLAMPS, IN						
			SULATION AND CLADDING SHEETS. #REMOVAL OF						
			ALL METAL SCRAPS, TEMPORARY SUPPORTS AND						
			ANY OTHER SCRAPS FROM WORK PLACE AND						
			DISPOSAL AS						
			PER DEWA ENGINEER INSTRUCTION.						
			·#HOUSEKEEPING # WORK PLACE AND DOWNSIDE						
			AREAS#DE-MOBILIZATION AND SITE CLEARANCE.						
			·#SUBMISSION O						
			F DETAILED WORK COMPLETION REPORT.						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			PHOTOS, ITP, WPS, WPQR, RIGGING TOOL						
			CERTIFICATES, NDT REPORTS, PWHT REPORT AND						
			ALL OTHER SUPPORT						
			ING DOCUMENTS #PARTY SHALL HAVE THE						
			EXPERIENCE FOR THE SIMILAR JOB/ WELD JOINTS						
			(MATERIAL GIVEN IN THE DRAWING BELOW) .#PO						
			FROM DE						
			WA AND ANY WELL-KNOWN COMPANY SHALL BE						
			SUBMITTED. CONTRACTOR SCOPE OF SUPPLY						
			·#TOOLS, TACKLES AND EQUIPMENT TO CARRY						
			OUT THE JOB.						
			·#MANPOWER ·#WELDING CONSUMABLES ·#ITP,						
			WPS, NDT PLAN, ERECTION PLAN & PWHT						
			PROCEDURES .#TEMPORARY SUPPORTS # DEWA						
			SCOPE :#INSULATI						
			ON MATERIAL AND CLADDING SHEET IF REQUIRE						
			*#SUPPLY OF NEW INNER, MIDDLE AND OUTER PR						
			TUBES & END PLATE#NDT INCLUDING RT, MPI, PT						
			AND PWHT#SCAFFOLDING -#CRANE -#FORKLIFT						
			WARRANTY -#A MINIMUM WARRANTY OF 12						
			MONTHS FOR WELD JOINTS AND WORKMANSHIP						
			SHALL PROVID						
			E BY THE CONTRACTOR STARTING FROM THE						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			DATE OF FINAL CLEARANCE FROM DEWA#IN						
			CASE OF ANY DAMAGE/DEFECT OF THE WORK						
			CARRIED OUT UNDE						
			R THIS CONTRACT WITHIN THIS WARRANTY						
			PERIOD, THE CONTRACTOR SHALL ATTEND AND						
			CARRY OUT THE NECESSARY REPAIR WORK AND						
			RECTIFY THE DEF						
			ECT WITHIN SHORT PERIOD WITHOUT AFFECTING						
			THE PRODUCTION OF ELECTRICITY AND WATER.						
			GENERAL TERMS & CONDITIONS TECHNICAL						
			SAFETY						
			DURING THE WORK: .#CONTRACTOR STAFF MUST						
			HAVE VALID GATE PASS BEFORE ENTERING THE						
			PLANT PREMISES#CONTRACTOR SHALL GIVE						
			DAILY TO						
			OL BOX TALK, RISK ASSESSMENT AND DYNAMIC						
			RISK ASSESSMENT TO THEIR STAFFS.						
			#CONTRACTOR STAFF INVOLVED IN ANY ACTIVITY						
			SHALL CONFIRM						
			THE AVAILABILITY OF LINE CLEARANCE (LC) AND						
			PERMIT TO WORK (PTW) BEFORE START OF ANY						
			WORK#CONTRACTOR STAFF MUST CHECK AND						
			VERIFY						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			OF THE ISOLATIONS BEFORE STARTING OF ANY						
			OVERHAULING WORK#THE CONTRACTOR SHALL						
			CHECK THE CONDITION SUITABLE TO CARRY OUT						
			THE WORK						
			. CONDUCT SITE SURVEY AND SAFETY INSPECTION						
			TO ASSESS THE WORKING ENVIRONMENT.						
			#CONTRACTOR SHALL ENSURE HOUSEKEEPING IS						
			DONE ON DAI						
			LY BASIS#CONTRACTOR SITE SUPERVISOR						
			SHALL BE CONTINUOUSLY PRESENT AT THE WORK						
			SITE TO SUPERVISE THE JOB. #THE CONTRACTOR						
			MUST EN						
			GAGE A QUALIFIED SAFETY OFFICER TO ENSURE						
			OBSERVANCE OF SAFETY AND SAFE WORKING						
			PRACTICES BY HIS MEN AT SITE AT ALL TIME. THE						
			SAFETY						
			SUPERVISOR SHALL KEEP ALL RECORDS (TBT,						
			RISK ASSESSMENT, HOT WORK PERMIT, PTW,						
			MSDS, ALL SAFETY RELATED DOCUMENTS#).						
			-#CONTRACTOR S						
			TAFF INVOLVED IN ANY ACTIVITY SHALL USE						
			APPROPRIATE PPES INCLUDING GLOVES, HELMET,						
			GOGGLES, SAFETY SHOE AND MASK ETC.						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			-#CONTRACTOR S						
			TAFF SHALL USE FULL BODY SAFETY HARNESS						
			WHEN WORKING AT HEIGHT#ONLY TESTED AND						
			CERTIFIED RIGGING TOOLS SHALL BE USED						
			DURING THE W						
			ORK. ALL THE RIGGING TOOLS MUST HAVE VALID						
			TEST CERTIFICATES AND IT MUST BE PRODUCE TO						
			DEWA FOREMAN/ ENGINEER UPON REQUEST.						
			-#CONTRA						
			CTOR MUST BE READY WITH ALL REQUIRED						
			RESOURCES TO EXECUTE THE WORK AS PER						
			AGREED SCOPE WORK DURING THE OUTAGE						
			SCHEDULE TO AVOID ANY						
			DELAY#DAILY HOT WORK PERMIT IS REQUIRED						
			BEFORE START OF ANY HOT WORK LIKE WELDING/						
			CUTTING/ GRINDING/DRILLING/HEATING ETC.						
			·#DURI						
			NG WELDING / CUTTING, ENSURE THAT WELDING						
			SPARK / CUTTING MATERIALS SHALL NOT FALL ON						
			NEARBY EQUIPMENT. ADEQUATE FIRE BLANKETS						
			SHALL						
			BE USED DURING WELDING AND CUTTING WORK.						
			.#NO ANY HOT WORK SHALL BE STARTED WITHOUT						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAI PRICE
			GETTING HOT WORK PERMIT AND WITHOUT FIRE						
			EXTING						
			UISHER NEAR THE WORK LOCATION#DAILY						
			CONFINED SPACE WORK PERMIT IS REQUIRED						
			BEFORE START OF ANY WORK INSIDE CONFINED						
			SPACE ·#CONTR						
			ACTOR SHALL ENSURE NO DISTURBANCE TO THE						
			NEARBY OPERATING PLANT / EQUIPMENT.						
			#CONTRACTOR IS RESPONSIBLE FOR ANY						
			DAMAGE OR EFFECT ON						
			INSTALLED OR OPERATING MACHINES						
			/EQUIPMENT/ PROPERTIES. :#ENSURE PROPER						
			HANDLING OF MATERIALS, TOOLS. SUITABLE						
			BELTS ARE TO BE WORN						
			TO AVOID TOOLS FROM FALLING#SAFETY SIGNS						
			SHALL BE PROVIDED AT WORK SITE AND						
			WHEREVER REQUIRED THE AREA IS TO BE						
			BARRICADED FOR S						
			AFETY AND TO PREVENT UNAUTHORIZED ENTRY.						
			-#CONTRACTOR STAFF ARE ALLOWED TO WORK						
			ONLY IN THE AUTHORIZED WORK PLACE						
			DESIGNATED BY DEWA						
			#CONTRACTOR STAFF ARE REQUIRED TO WEAR						





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023

CLOSING TIME : 10:00:00

SL NO	ITEM CODE	SERVICE ID	DESCRIPTION	QTY	UOM	BRAND/ORIGIN	WARRANTY	UNIT PRICE	TOTAL PRICE
			THEIR COMPANY UNIFORM & CARRY THEIR GATE						
			PASS IDS DURING THE WORK INSIDE DEWA						
			PREMISES. ·#						
			ALL THE SAFETY AND SECURITY PROCEDURES OF						
			DEWA SHALL BE STRICTLY ADHERED#IN CASE						
			ANY ACCIDENT/NEAR MISS/						

TOTAL AMOUNT IN WORDS: TOTAL AMOUNT:

SPECIAL NOTES / INSTRUCTIONS:

HP/MP CONTROL VALVE PR TUBE REPLACEMENT WORK For more information contact Mr. KaliyamoorthiV 043226919 052 9126916 KaliyamoorthiV @ dewa.gov.ae

STANDARD TERMS & CONDITIONS

- 1) Prices should be 'DDP' delivery duty paid at DEWA stores.
- 2) Quotation to be submitted only in local currency U.A.E Dirhams
- 3) DEWA Standard payment terms is '30 days credit' from the date of acceptance of material
- 4) No DEWA staff or his or her relatives up to third degree should have ownership or partnership in your company, and your participation in DEWA tenders / RFQs should not constitute a Conflict or perceived Conflict of Interest.
- 5) The offered product and/ or services in the Quotation, shall be conforming and in accordance with DEWA Energy Management Policy & EnMS Manual.

Page11 of 12





RFQ NUMBER : 2412301070

DATE : 21.08.2023 **REQ No** : 1032301754

REQ TITLE : HP/MP CONTROL VALVE PR

DELIVERY LOCATION

CLOSING DATE : 01.09.2023 **CLOSING TIME** : 10:00:00

SUPPLIER'S REMARKS:

SUPPLIER'S SIGNATURE AND STAMP